

WORK ORDER FORM

To: **MADHURAM ENTERPRISES**
 03, Sejal Apt., Dattapada X-Road No.02
 Borivali (E)
 MUMBAI 400066 Phone: 9819408257
 GSTIN : 27AESPN7117D1ZA

WO Number : 4700157988
 WO Date : 28.04.2025
 Kalyan - Bhiwandi Road,
 Survey No.98 & 99, Village Gove, Taluka Bhiwandi, Dist.Thane
 421308

Description of Work :

Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value
1	PLUMBING & SANITATION WORK Building : Oakwood Kalyan	1	AU		16,564,933.60
(1)	Sac : 995462 - Fixing of flr mounting type European WC SANITARY FIXTURES & FITTINGS (INSTALLATION) Fixing, testing and commissioning of white vitreous china floor mounting type European water closet with built-in exposed cistern of capacity 3 & 6 litres with C.P. bolts, nuts, supporting arrangements, bakelite seat & cover with C.P. hinges & rubber buffers, complete with all accessories. Including cutting & making good the walls & floors wherever required.	396	NOS	297.50	117,810.00
				CGST Inv(9.00%)	INR 10,602.90
				SGST-Inv(9.00%)	INR 10,602.90
(2)	Sac : 995462 - T,C&H of flr mounting type European WC	396	NOS	52.50	20,790.00
				CGST Inv(9.00%)	INR 1,871.10
				SGST-Inv(9.00%)	INR 1,871.10
(3)	Sac : 995462 - Fixing of flr mounting type EWC Fixing, testing and commissioning of white vitreous china floor mounting type EWC or Anglo Indian water closet without cistern with C.P. bolts, nuts, supporting arrangements, bakelite seat & cover with C.P. hinges & rubber buffers, complete with all accessories. Including cutting & making good the walls & floors wherever required. (For Gr. Toilet)	1	NOS	255.00	255.00
				CGST Inv(9.00%)	INR 22.95
				SGST-Inv(9.00%)	INR 22.95
(4)	Sac : 995462 - T,C&H of flr mounting type EWC	1	NOS	45.00	45.00
				CGST Inv(9.00%)	INR 4.05
				SGST-Inv(9.00%)	INR 4.05

Corporate Addr.:514, Dalalal Tower, 211 FPJ Marg,Nariman Point,
 Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value
(5)	Sac : 995462 - Fixing of exposed plastic cistern Fixing, testing and commissioning of exposed plastic cistern for WC, complete with all necessary fittings, flush pipes & accessories including all supports and making good. cistern dual flush, outlet from tank to w.c. (For Gr. Toilet)	1	NOS	212.50	212.50
				CGST Inv(9.00%)	INR 19.13
				SGST-Inv(9.00%)	INR 19.13
(6)	Sac : 995462 - T,C&H of exposed plastic cistern	1	NOS	37.50	37.50
				CGST Inv(9.00%)	INR 3.38
				SGST-Inv(9.00%)	INR 3.38
(7)	Sac : 995462 - Fixing of Single lever wall mixer Fixing, testing & commissioning of Exposed Single lever wall mixer assembly with 150 mm long bend pipe OR hand shower with flexible pipe / shower rail and wall flanges complete as a full set as required.	298	NOS	191.25	56,992.50
				CGST Inv(9.00%)	INR 5,129.33
				SGST-Inv(9.00%)	INR 5,129.33
(8)	Sac : 995462 - T,C&H of Single lever wall mixer	298	NOS	33.75	10,057.50
				CGST Inv(9.00%)	INR 905.18
				SGST-Inv(9.00%)	INR 905.18
(9)	Sac : 995462 - Fixing of single lever sink tap Fixing, testing and commissioning of exposed single lever sink tap wall or table mounted with flange complete with all necessary fittings, and making good.	198	NOS	170.00	33,660.00
				CGST Inv(9.00%)	INR 3,029.40
				SGST-Inv(9.00%)	INR 3,029.40
(10)	Sac : 995462 - T,C&H of single lever sink tap	198	NOS	30.00	5,940.00
				CGST Inv(9.00%)	INR 534.60
				SGST-Inv(9.00%)	INR 534.60
(11)	Sac : 995462 - Fixing of ABS Rinsing spray Fixing, testing & commissioning of ABS Rinsing spray / health faucet / Jet Plate etc. with regulator of approved quality with plastic flexible pipe 1.0 m long, wall hooked complete as required.	397	NOS	85.00	33,745.00

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	3,037.05
				SGST-Inv(9.00%)	INR	3,037.05
(12)	Sac : 995462 - T,C&H of ABS Rinsing spray	397	NOS	15.00		5,955.00
				CGST Inv(9.00%)	INR	535.95
				SGST-Inv(9.00%)	INR	535.95
(13)	Sac : 995462 - Fixing of wall hung flat back wash basin Fixing, testing and commissioning of vitreous china wall hung flat back wash basin with C.I./M.S. brackets duly painted, C.P. brass waste, 32 mm diameter PP / C.P. cast brass bottle trap with extension piece and wall flange complete, including cutting and making good the walls/floors wherever required.	397	NOS	340.00		134,980.00
				CGST Inv(9.00%)	INR	12,148.20
				SGST-Inv(9.00%)	INR	12,148.20
(14)	Sac : 995462 - T,C&H of wall hung flat back wash basin	397	NOS	60.00		23,820.00
				CGST Inv(9.00%)	INR	2,143.80
				SGST-Inv(9.00%)	INR	2,143.80
(15)	Sac : 995462 - Fixing of C.P. brass pillar cock Fixing, testing and commissioning of C.P. brass pillar cock #including providing & fixing connector" for pillar cock complete as required.	397	NOS	148.75		59,053.75
				CGST Inv(9.00%)	INR	5,314.84
				SGST-Inv(9.00%)	INR	5,314.84
(16)	Sac : 995462 - T,C&H of C.P. brass pillar cock	397	NOS	26.25		10,421.25
				CGST Inv(9.00%)	INR	937.91
				SGST-Inv(9.00%)	INR	937.91
(17)	Sac : 995462 - Fixing of water heater 3 litres (4.5KW) Fixing, testing & commissioning of instant / storage type water heater of approved shade with copper / SS container, glasswool insulation, stove enamelled M.S jacket, thermostatically controlled inner heater with pilot neon lamps, suitable for working pressure of 5/ 8 kg/sqcm with suitable KW heater coil, 240 volts, single phase supply complete as required. Including providing and fixing of g.i. brackets, anchor fastener, g.i. nut-bolt-washer etc. complete. (Bathroom heater fixing above false ceiling)	298	NOS	680.00		202,640.00

Corporate Addr.:514, Dalmal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	18,237.60
				SGST-Inv(9.00%)	INR	18,237.60
(18)	Sac : 995462 - T,C&H of water heater 3 litres (4.5KW) Fixing, testing and commissioning of C.P. brass Bib cock with C.P. wall flange, Washer etc. complete as required. (for Refuge flat / S. Toilet etc.)	298	NOS	120.00	35,760.00	
				CGST Inv(9.00%)	INR	3,218.40
				SGST-Inv(9.00%)	INR	3,218.40
(19)	Sac : 995462 - Fixing of C.P. brass Bib cock Fixing, testing and commissioning of C.P. brass Bib cock with C.P. wall flange, Nut and Washer etc. complete as required. (for heater inlet, health faucet, exposed flush tank inlet, W/M inlet, Purifier inlet etc.) W/M & Purifier inlet Angle cock with coupling and plug.	2	NOS	85.00	170.00	
				CGST Inv(9.00%)	INR	15.30
				SGST-Inv(9.00%)	INR	15.30
(20)	Sac : 995462 - T,C&H of C.P. brass Bib cock	2	NOS	15.00	30.00	
				CGST Inv(9.00%)	INR	2.70
				SGST-Inv(9.00%)	INR	2.70
(21)	Sac : 995462 - Fixing of C.P. brass angle valve Fixing, testing and commissioning of C.P. brass angle valve with C.P. wall flange, Nut and Washer etc. complete as required. (for heater inlet, health faucet, exposed flush tank inlet, W/M inlet, Purifier inlet etc.) W/M & Purifier inlet Angle cock with coupling and plug.	1,488	NOS	85.00	126,480.00	
				CGST Inv(9.00%)	INR	11,383.20
				SGST-Inv(9.00%)	INR	11,383.20
(22)	Sac : 995462 - T,C&H of C.P. brass angle valve	1,488	NOS	15.00	22,320.00	
				CGST Inv(9.00%)	INR	2,008.80
				SGST-Inv(9.00%)	INR	2,008.80
(23)	Sac : 995462 - Fixing of S.S. 5" dia. round jali Providing, Fixing, testing and commissioning of S.S. 5" dia. round jali for floor traps etc. complete as required. (For refuge flats) 5" Round (Glossy finish) 2PC	3	NOS	170.00	510.00	
				CGST Inv(9.00%)	INR	45.90
				SGST-Inv(9.00%)	INR	45.90
(24)	Sac : 995462 - T,C&H of S.S. 5" dia. round jali	3	NOS	30.00	90.00	
				CGST Inv(9.00%)	INR	8.10

Corporate Addr.:514, Dalmal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				SGST-Inv(9.00%)	INR	8.10
(25)	Sac : 995462 - Fixing of 5" x 5" cockroach trap S.S. Providing, Fixing, testing and commissioning of 5" x 5" cockroach trap S.S. Jali for floor traps etc. complete as required. (for Kitchen sinks, pantry etc.) 5" x 5" Square (Glossy finish), 18 gauge, Cockroach Trap	198	NOS	318.75	63,112.50	
				CGST Inv(9.00%)	INR	5,680.13
				SGST-Inv(9.00%)	INR	5,680.13
(26)	Sac : 995462 - T,C&H of 5" x 5" cockroach trap S.S. J	198	NOS	56.25	11,137.50	
				CGST Inv(9.00%)	INR	1,002.38
				SGST-Inv(9.00%)	INR	1,002.38
(27)	Sac : 995462 - Fixing of 5" x 5" Square (Matt finish) Providing, Fixing, testing and commissioning of 5" x 5" Square (Matt finish), 18 gauge 2PC (For Bathrooms, balcony / deck drain)	596	NOS	191.25	113,985.00	
				CGST Inv(9.00%)	INR	10,258.65
				SGST-Inv(9.00%)	INR	10,258.65
(28)	Sac : 995462 - T,C&H of 5" x 5" Square (Matt finish)	596	NOS	33.75	20,115.00	
				CGST Inv(9.00%)	INR	1,810.35
				SGST-Inv(9.00%)	INR	1,810.35

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value
(29)	Sac : 995462 - Supply of 15 mm dia CPVC pipe COLD & HOT WATER SUPPLY (INTERNAL) Concealed Piping (Hot & Cold water supply in Toilets and Kitchens) Providing, fixing, jointing and testing in position CPVC (Chlorinated Poly Vinyl Chloride) water supply pipes with fittings as per CTS SDR 11 (operating pressure - 7 Bar @ 82 Deg C and 28 Bar @ 23 Deg C). Pipes shall be joined using solvent welded CPVC fittings i.e. Tees, Elbows, Couplers, Unions, Reducers, bushings etc. including transition fittings i.e. Brass Adaptors / Elbows (both Male & Female threaded) conforming to ASTM D-2846, ASTM F441 with only CPVC solvent cement conforming to ASTM F-493. Cost shall be inclusive of (a) Making chasing in wall for the pipe, making good the same after piping and pressure testing by using 1:1 Geru mixed cement mortar including all Civil materials. or (b) Fixing/supporting the pipes (& fittings) at wall/ceiling level supported by split clamp with rubber lining type hangers etc, as per specification. PVC pipe sleeves of suitable higher size shall be provided wherever the pipes are crossing the walls / floors slab. (c) Pressure testing of all concealed water supply pipes as per requirement (5 kg/cm ² for Gravity system & 10 kg/cm ² for Hydropneumatic system) (d) Curing of chasing finishing works for 7 days. For hot & Cold water piping in toilets. Nitrile rubber insulation for exposed Hot water pipes in ceiling or in shaft or on terrace. (15 to 25mm - 9mm thk. / 32 to 80mm = 13mm thk.)	4,500	M	120.25	541,125.00
(30)	Sac : 995462 - Inst of 15 mm dia CPVC pipe	4,500	M	CGST Inv(9.00%) SGST-Inv(9.00%)	INR 48,701.25 INR 48,701.25
(31)	Sac : 995462 - T&C of 15 mm dia CPVC pipe	4,500	M	37.00 CGST Inv(9.00%) SGST-Inv(9.00%)	166,500.00 INR 14,985.00 INR 14,985.00
(32)	Sac : 995462 - Handover of 15 mm dia CPVC pipe	4,500	M	18.50 CGST Inv(9.00%) SGST-Inv(9.00%)	83,250.00 INR 7,492.50 INR 7,492.50
(33)	Sac : 995462 - Supply of 20 mm dia CPVC pipe	80	M	9.25 CGST Inv(9.00%) SGST-Inv(9.00%)	41,625.00 INR 3,746.25 INR 3,746.25
					14,040.00



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	1,263.60
				SGST-Inv(9.00%)	INR	1,263.60
(34)	Sac : 995462 - Inst of 20 mm dia CPVC pipe	80	M	54.00	4,320.00	
				CGST Inv(9.00%)	INR	388.80
				SGST-Inv(9.00%)	INR	388.80
(35)	Sac : 995462 - T&C of 20 mm dia CPVC pipe	80	M	27.00	2,160.00	
				CGST Inv(9.00%)	INR	194.40
				SGST-Inv(9.00%)	INR	194.40
(36)	Sac : 995462 - Handover of 20 mm dia CPVC pipe	80	M	13.50	1,080.00	
				CGST Inv(9.00%)	INR	97.20
				SGST-Inv(9.00%)	INR	97.20
(37)	Sac : 995462 - Supply of 50mm dia GI pipe	20	M	559.00	11,180.00	
	G.I. PIPING					
	Providing, fixing, jointing and testing in position the following heavy class (Class-C) G.I. pipes conforming to IS:1239 cut to required lengths including all necessary fittings (All fittings shall conform to IS:1879 - part 1 to 10) and specials such as bends, tees, unions, reducers, flanges & plugs etc. Fixing at wall/ceiling level supported by galvanized clamps, hangers etc, as per specification.					
	Threading, jointing, and making proper connections.					
	For pump delivery lines only 'C' type Fabricated Hotdip galvanised brackets with PVC coated 'U' clamps shall be used for vertical and horizontal supports as per details given below					
	Vertical support spacing (Center to Center) 'C' type Fabricated Hotdip galvanised brackets with GI 'U' clamps - shall be as follows - 15mm = 1800mm / 20mm & 25mm = 2000mm / 32mm to 50mm = 2800mm / 65mm & above = 3000mm					
	Horizontal supports spacing (Center to Center) shall be as follows - 15mm = 1250mm / 20mm & 25mm = 2000mm / 32mm to 50mm = 2200mm / 65mm & above = 2500mm. Above are manufacturer's standards, but for vertical supports use 3 brackets / floor for residential building and 4 brackets / floor for commercial building or 1 m c/c whichever is less. For horizontal supports use 1.25 m c/c for all sizes.					
	For exposed piping for TMC, Pump Delivery-Suction, Tank Interconnection etc. O.H. Tank to Podium loop lines					
				CGST Inv(9.00%)	INR	1,006.20
				SGST-Inv(9.00%)	INR	1,006.20

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
(38)	Sac : 995462 - Inst of 50mm dia GI pipe	20	M	172.00	3,440.00	
				CGST Inv(9.00%)	INR	309.60
				SGST-Inv(9.00%)	INR	309.60
(39)	Sac : 995462 - T&C of 50mm dia GI pipe	20	M	86.00	1,720.00	
				CGST Inv(9.00%)	INR	154.80
				SGST-Inv(9.00%)	INR	154.80
(40)	Sac : 995462 - Handover of 50mm dia GI pipe	20	M	43.00	860.00	
				CGST Inv(9.00%)	INR	77.40
				SGST-Inv(9.00%)	INR	77.40
(41)	Sac : 995462 - Supply of 65mm dia GI pipe	150	M	708.50	106,275.00	
				CGST Inv(9.00%)	INR	9,564.75
				SGST-Inv(9.00%)	INR	9,564.75
(42)	Sac : 995462 - Inst of 65mm dia GI pipe	150	M	218.00	32,700.00	
				CGST Inv(9.00%)	INR	2,943.00
				SGST-Inv(9.00%)	INR	2,943.00
(43)	Sac : 995462 - T&C of 65mm dia GI pipe	150	M	109.00	16,350.00	
				CGST Inv(9.00%)	INR	1,471.50
				SGST-Inv(9.00%)	INR	1,471.50
(44)	Sac : 995462 - Handover of 65mm dia GI pipe	150	M	54.50	8,175.00	
				CGST Inv(9.00%)	INR	735.75
				SGST-Inv(9.00%)	INR	735.75
(45)	Sac : 995462 - Supply of 80mm dia GI pipe	150	M	893.75	134,062.50	
				CGST Inv(9.00%)	INR	12,065.63
				SGST-Inv(9.00%)	INR	12,065.63
(46)	Sac : 995462 - Inst of 80mm dia GI pipe	150	M	275.00	41,250.00	
				CGST Inv(9.00%)	INR	3,712.50
				SGST-Inv(9.00%)	INR	3,712.50
(47)	Sac : 995462 - T&C of 80mm dia GI pipe	150	M	137.50	20,625.00	
				CGST Inv(9.00%)	INR	1,856.25
				SGST-Inv(9.00%)	INR	1,856.25

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
(48)	Sac : 995462 - Handover of 80mm dia GI pipe	150	M	68.75	10,312.50	
				CGST Inv(9.00%)	INR	928.13
				SGST-Inv(9.00%)	INR	928.13
(49)	Sac : 995462 - Supply of 100mm dia GI pipe	6	M	1,202.50	7,215.00	
				CGST Inv(9.00%)	INR	649.35
				SGST-Inv(9.00%)	INR	649.35
(50)	Sac : 995462 - Inst of 100mm dia GI pipe	6	M	370.00	2,220.00	
				CGST Inv(9.00%)	INR	199.80
				SGST-Inv(9.00%)	INR	199.80
(51)	Sac : 995462 - T&C of 100mm dia GI pipe	6	M	185.00	1,110.00	
				CGST Inv(9.00%)	INR	99.90
				SGST-Inv(9.00%)	INR	99.90
(52)	Sac : 995462 - Handover of 100mm dia GI pipe	6	M	92.50	555.00	
				CGST Inv(9.00%)	INR	49.95
				SGST-Inv(9.00%)	INR	49.95
(53)	Sac : 995462 - Supply of 150mm dia GI pipe	12	M	1,690.00	20,280.00	
				CGST Inv(9.00%)	INR	1,825.20
				SGST-Inv(9.00%)	INR	1,825.20
(54)	Sac : 995462 - Inst of 150mm dia GI pipe	12	M	520.00	6,240.00	
				CGST Inv(9.00%)	INR	561.60
				SGST-Inv(9.00%)	INR	561.60
(55)	Sac : 995462 - T&C of 150mm dia GI pipe	12	M	260.00	3,120.00	
				CGST Inv(9.00%)	INR	280.80
				SGST-Inv(9.00%)	INR	280.80
(56)	Sac : 995462 - Handover of 150mm dia GI pipe	12	M	130.00	1,560.00	
				CGST Inv(9.00%)	INR	140.40
				SGST-Inv(9.00%)	INR	140.40

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value
(57)	Sac : 995462 - Supply of 50mm dia GI pipe Providing, fixing, jointing and testing in position the following heavy class (Class-C) G.I. pipes conforming to IS:1239 cut to required lengths with Zoloto-M or 'R' brand GI fittings as per specifications and complete with fittings such as sockets, unions, reducers long or short bends, elbows, nipples flanges, checknuts, clamps etc. Scope includes, Flanged connections with G.I. puddle sleeves provided in RCC walls with providing and fixing of required G.I. flanges, G.I. Nut-Bolt & Washers & rubber packing's. Scope also includes Excavation of required width & depth, Pressure testing of piping and providing protection to embedded G.I. Pipes & fittings by wrapping hessian cloth over two coats of bitumen, & back filling of trench complete as required. For under ground piping for TMC including all Civil materials. (excavation, backfilling quantity considered separately)	10	M	487.50	4,875.00
				CGST Inv(9.00%)	INR 438.75
				SGST-Inv(9.00%)	INR 438.75
(58)	Sac : 995462 - Inst of 50mm dia GI pipe	10	M	150.00	1,500.00
				CGST Inv(9.00%)	INR 135.00
				SGST-Inv(9.00%)	INR 135.00
(59)	Sac : 995462 - T&C of 50mm dia GI pipe	10	M	75.00	750.00
				CGST Inv(9.00%)	INR 67.50
				SGST-Inv(9.00%)	INR 67.50
(60)	Sac : 995462 - Handover of 50mm dia GI pipe	10	M	37.50	375.00
				CGST Inv(9.00%)	INR 33.75
				SGST-Inv(9.00%)	INR 33.75

Corporate Addr.:514, Dalmal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value
(61)	Sac : 995462 - Supply of 50mm dia UPVC pipe sch 40 Providing, fixing, jointing and testing in position the following U-PVC pressure Pipes Sch. 40 as per ASTM D 1785 and plain end (pasted). Cut to required lengths including all necessary fittings and specials such as bends, tees, unions, reducers, plugs etc in U-PVC pressure fittings Sch. 80 as per ASTM D 1785 Jointing with solvent cement. Use Cleaner, Primer and solvent for pipe dia. 50mm and more. Scope includes, Flanged connections with G.I. puddle sleeves provided in RCC walls with providing and fixing of required G.I. flanges, G.I. Nut-Bolt & Washers & rubber packing's. Scope also includes Pressure testing of piping, encasing of pipes with CC M-15 & back filling of trench complete as required. For under ground piping for, Irrigation, STP, Sump pumps , Tanker inlet, DCB etc. including all Civil materials. (excavation, concrete, backfilling quantity considered separately)	10	M	175.50	1,755.00
				CGST Inv(9.00%)	INR 157.95
				SGST-Inv(9.00%)	INR 157.95
(62)	Sac : 995462 - Inst of 50mm dia UPVC pipe sch 40	10	M	54.00	540.00
				CGST Inv(9.00%)	INR 48.60
				SGST-Inv(9.00%)	INR 48.60
(63)	Sac : 995462 - T&C of 50mm dia UPVC pipe sch 40	10	M	27.00	270.00
				CGST Inv(9.00%)	INR 24.30
				SGST-Inv(9.00%)	INR 24.30
(64)	Sac : 995462 - Handover of 50mm dia UPVC pipe sch 40	10	M	13.50	135.00
				CGST Inv(9.00%)	INR 12.15
				SGST-Inv(9.00%)	INR 12.15
(65)	Sac : 995462 - Supply of 80mm dia UPVC pipe sch 40	400	M	390.00	156,000.00
				CGST Inv(9.00%)	INR 14,040.00
				SGST-Inv(9.00%)	INR 14,040.00
(66)	Sac : 995462 - Inst of 80mm dia UPVC pipe sch 40	400	M	120.00	48,000.00
				CGST Inv(9.00%)	INR 4,320.00
				SGST-Inv(9.00%)	INR 4,320.00
(67)	Sac : 995462 - T&C of 80mm dia UPVC pipe sch 40	400	M	60.00	24,000.00

Corporate Addr.:514, Dalalal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	2,160.00
				SGST-Inv(9.00%)	INR	2,160.00
(68)	Sac : 995462 - Handover of 80mm dia UPVC pipe sch 40	400	M	30.00	12,000.00	
				CGST Inv(9.00%)	INR	1,080.00
				SGST-Inv(9.00%)	INR	1,080.00
(69)	Sac : 995462 - Supply of 100mm dia UPVC pipe sch 40	10	M	552.50	5,525.00	
				CGST Inv(9.00%)	INR	497.25
				SGST-Inv(9.00%)	INR	497.25
(70)	Sac : 995462 - Inst of 100mm dia UPVC pipe sch 40	10	M	170.00	1,700.00	
				CGST Inv(9.00%)	INR	153.00
				SGST-Inv(9.00%)	INR	153.00
(71)	Sac : 995462 - T&C of 100mm dia UPVC pipe sch 40	10	M	85.00	850.00	
				CGST Inv(9.00%)	INR	76.50
				SGST-Inv(9.00%)	INR	76.50
(72)	Sac : 995462 - Handover of 100mm dia UPVC pipe sch 40	10	M	42.50	425.00	
				CGST Inv(9.00%)	INR	38.25
				SGST-Inv(9.00%)	INR	38.25
Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point, Mumbai- 400021, Tel No.						
						

Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value
(73)	<p>Sac : 995462 - Supply of 15mm dia UPVC pipe sch 40</p> <p>Providing, fixing, jointing and testing in position the following U-PVC pressure Pipes Sch. 40 as per ASTM D 1785 and plain end (pasted). Cut to required lengths including all necessary fittings and specials such as bends, tees, unions, reducers, plugs etc in U-PVC pressure fittings Sch. 80 as per ASTM D 1785 Jointing with solvent cement. Including G.I. Brackets with PVC coated 'U' clamps fixing at wall/ ceiling level, hangers etc. as per specification. Cutting hole in wall and making good the same with cement concrete M-15 complete as required. pvc pipe sleeve of larger diameter shall be provided wherever the pipes crossing the walls / floor slab and sealing the sleeves as per consultants requirement. Use Cleaner, Primer and solvent for pipe dia. 50mm and more.</p> <p>Brass insert male adaptor shall be used for toilet / kit, inlet to branch pipe connection (15mm & 20mm). For terrace loop branch valves, metal insert adaptors shall be used. For suspended piping (other than loop) GI split clamp with rubber lining with rod/nut/washer etc. shall be used as per required spacing. Every 5 mtr. Interval G.I. bracket (including painting) with pvc coated clamps shall be used. Scope also includes miscellaneous works like # U.G. & O.H. tank overflow, drain (Fire/Flush/Domestic) , 25 dia. loop air piping with supports, mosquito nets etc. for vertical supports use 3 brackets / floor for residential building and 4 brackets / floor for commercial building or 1 m c/c whichever is less.</p> <p>Additional supports shall be provided for water supply branch pipes in shaft, which are more than 500mm long. (2 supports, if branch is more than 1000mm long)</p> <p>For vertical lines, Terrace loop & branch pipes, 'C' type Fabricated Hotdip galvanised brackets with PVC coated 'U' clamps shall be used.</p> <p>Horizontal supports spacing (Center to Center) shall be as follows - 15mm and 20mm = 500mm / 25mm = 600mm / 32mm = 700mm / 40mm = 800mm / 50mm = 900mm and 65mm and bigger dia. = 1000mm.</p> <p>(For External water supply downtake / Uptake piping in shaft, staircase servant toilet open piping, Terrace loop, STP line, DCB line, tanker line, sump pump lines etc.)</p>	1,470	M	133.25	195,877.50
(74)	<p>Sac : 995462 - Inst of 15mm dia UPVC pipe sch 40</p>	1,470	M	41.00	60,270.00
				CGST Inv(9.00%)	INR 17,628.98
				SGST-Inv(9.00%)	INR 17,628.98
(75)	<p>Sac : 995462 - T&C of 15mm dia UPVC pipe sch 40</p>	1,470	M	20.50	30,135.00
				CGST Inv(9.00%)	INR 5,424.30
				SGST-Inv(9.00%)	INR 5,424.30

Corporate Addr.:514, Dalalal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	2,712.15
				SGST-Inv(9.00%)	INR	2,712.15
(76)	Sac : 995462 - Handover of 15mm dia UPVC pipe sch 40	1,470	M	10.25		15,067.50
				CGST Inv(9.00%)	INR	1,356.08
				SGST-Inv(9.00%)	INR	1,356.08
(77)	Sac : 995462 - Supply of 20mm dia UPVC pipe sch 40	675	M	136.50		92,137.50
				CGST Inv(9.00%)	INR	8,292.38
				SGST-Inv(9.00%)	INR	8,292.38
(78)	Sac : 995462 - Inst of 20mm dia UPVC pipe sch 40	675	M	42.00		28,350.00
				CGST Inv(9.00%)	INR	2,551.50
				SGST-Inv(9.00%)	INR	2,551.50
(79)	Sac : 995462 - T&C of 20mm dia UPVC pipe sch 40	675	M	21.00		14,175.00
				CGST Inv(9.00%)	INR	1,275.75
				SGST-Inv(9.00%)	INR	1,275.75
(80)	Sac : 995462 - Handover of 20mm dia UPVC pipe sch 40	675	M	10.50		7,087.50
				CGST Inv(9.00%)	INR	637.88
				SGST-Inv(9.00%)	INR	637.88
(81)	Sac : 995462 - Supply of 25mm dia UPVC pipe sch 40	1,400	M	162.50		227,500.00
				CGST Inv(9.00%)	INR	20,475.00
				SGST-Inv(9.00%)	INR	20,475.00
(82)	Sac : 995462 - Inst of 25mm dia UPVC pipe sch 40	1,400	M	50.00		70,000.00
				CGST Inv(9.00%)	INR	6,300.00
				SGST-Inv(9.00%)	INR	6,300.00
(83)	Sac : 995462 - T&C of 25mm dia UPVC pipe sch 40	1,400	M	25.00		35,000.00
				CGST Inv(9.00%)	INR	3,150.00
				SGST-Inv(9.00%)	INR	3,150.00
(84)	Sac : 995462 - Handover of 25mm dia UPVC pipe sch 40	1,400	M	12.50		17,500.00
				CGST Inv(9.00%)	INR	1,575.00

Corporate Addr.:514, Dalmal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				SGST-Inv(9.00%)	INR	1,575.00
(85)	Sac : 995462 - Supply of 32mm dia UPVC pipe sch 40	1,350	M	191.10	257,985.00	
				CGST Inv(9.00%)	INR	23,218.65
				SGST-Inv(9.00%)	INR	23,218.65
(86)	Sac : 995462 - Inst of 32mm dia UPVC pipe sch 40	1,350	M	58.80	79,380.00	
				CGST Inv(9.00%)	INR	7,144.20
				SGST-Inv(9.00%)	INR	7,144.20
(87)	Sac : 995462 - T&C of 32mm dia UPVC pipe sch 40	1,350	M	29.40	39,690.00	
				CGST Inv(9.00%)	INR	3,572.10
				SGST-Inv(9.00%)	INR	3,572.10
(88)	Sac : 995462 - Handover of 32mm dia UPVC pipe sch 40	1,350	M	14.70	19,845.00	
				CGST Inv(9.00%)	INR	1,786.05
				SGST-Inv(9.00%)	INR	1,786.05
(89)	Sac : 995462 - Supply of 40mm dia UPVC pipe sch 40	800	M	232.05	185,640.00	
				CGST Inv(9.00%)	INR	16,707.60
				SGST-Inv(9.00%)	INR	16,707.60
(90)	Sac : 995462 - Inst of 40mm dia UPVC pipe sch 40	800	M	71.40	57,120.00	
				CGST Inv(9.00%)	INR	5,140.80
				SGST-Inv(9.00%)	INR	5,140.80
(91)	Sac : 995462 - T&C of 40mm dia UPVC pipe sch 40	800	M	35.70	28,560.00	
				CGST Inv(9.00%)	INR	2,570.40
				SGST-Inv(9.00%)	INR	2,570.40
(92)	Sac : 995462 - Handover of 40mm dia UPVC pipe sch 40	800	M	17.85	14,280.00	
				CGST Inv(9.00%)	INR	1,285.20
				SGST-Inv(9.00%)	INR	1,285.20
(93)	Sac : 995462 - Supply of 50mm dia UPVC pipe sch 40	663	M	260.00	172,380.00	
				CGST Inv(9.00%)	INR	15,514.20
				SGST-Inv(9.00%)	INR	15,514.20
(94)	Sac : 995462 - Inst of 50mm dia UPVC pipe sch 40	663	M	80.00	53,040.00	

Corporate Addr.:514, Dalmal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	4,773.60
				SGST-Inv(9.00%)	INR	4,773.60
(95)	Sac : 995462 - T&C of 50mm dia UPVC pipe sch 40	663	M	40.00	26,520.00	
				CGST Inv(9.00%)	INR	2,386.80
				SGST-Inv(9.00%)	INR	2,386.80
(96)	Sac : 995462 - Handover of 50mm dia UPVC pipe sch 40	663	M	20.00	13,260.00	
				CGST Inv(9.00%)	INR	1,193.40
				SGST-Inv(9.00%)	INR	1,193.40
(97)	Sac : 995462 - Supply of 65mm dia UPVC pipe sch 40	210	M	414.70	87,087.00	
				CGST Inv(9.00%)	INR	7,837.83
				SGST-Inv(9.00%)	INR	7,837.83
(98)	Sac : 995462 - Inst of 65mm dia UPVC pipe sch 40	210	M	127.60	26,796.00	
				CGST Inv(9.00%)	INR	2,411.64
				SGST-Inv(9.00%)	INR	2,411.64
(99)	Sac : 995462 - T&C of 65mm dia UPVC pipe sch 40	210	M	63.80	13,398.00	
				CGST Inv(9.00%)	INR	1,205.82
				SGST-Inv(9.00%)	INR	1,205.82
(100)	Sac : 995462 - Handover of 65mm dia UPVC pipe sch 40	210	M	31.90	6,699.00	
				CGST Inv(9.00%)	INR	602.91
				SGST-Inv(9.00%)	INR	602.91
(101)	Sac : 995462 - Supply of 80mm dia UPVC pipe sch 40	472	M	495.95	234,088.40	
				CGST Inv(9.00%)	INR	21,067.96
				SGST-Inv(9.00%)	INR	21,067.96
(102)	Sac : 995462 - Inst of 80mm dia UPVC pipe sch 40	472	M	152.60	72,027.20	
				CGST Inv(9.00%)	INR	6,482.45
				SGST-Inv(9.00%)	INR	6,482.45
(103)	Sac : 995462 - T&C of 80mm dia UPVC pipe sch 40	472	M	76.30	36,013.60	
				CGST Inv(9.00%)	INR	3,241.22

Corporate Addr.:514, Dalmal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				SGST-Inv(9.00%)	INR	3,241.22
(104)	Sac : 995462 - Handover of 80mm dia UPVC pipe sch 40	472	M	38.15	18,006.80	
				CGST Inv(9.00%)	INR	1,620.61
				SGST-Inv(9.00%)	INR	1,620.61
(105)	Sac : 995462 - Supply of 100mm dia UPVC pipe sch 40	264	M	694.20	183,268.80	
				CGST Inv(9.00%)	INR	16,494.19
				SGST-Inv(9.00%)	INR	16,494.19
(106)	Sac : 995462 - Inst of 100mm dia UPVC pipe sch 40	264	M	213.60	56,390.40	
				CGST Inv(9.00%)	INR	5,075.14
				SGST-Inv(9.00%)	INR	5,075.14
(107)	Sac : 995462 - T&C of 100mm dia UPVC pipe sch 40	264	M	106.80	28,195.20	
				CGST Inv(9.00%)	INR	2,537.57
				SGST-Inv(9.00%)	INR	2,537.57
(108)	Sac : 995462 - Handover of 100mm dia UPVC pipe sch 40	264	M	53.40	14,097.60	
				CGST Inv(9.00%)	INR	1,268.78
				SGST-Inv(9.00%)	INR	1,268.78
(109)	Sac : 995462 - Supply of 15mm dia ball valve Providing & fixing full way lever operated forged brass ball valve of brass body with forged brass hard chromeplated steel ball tested to a pressure not less than 20 Kg / sqcm with threaded / flanged joints complete with nuts, bolts, gaskets, washers etc. For all Water supply branch on terrace / podium level and in shafts, Terrace loop, Hydropneumatic loop, U.G. & O.H. tank drain {Fire/Flush/Domestic}, pump priming, before & after PRV, below air valve, Municipal etc. PVC (male / female) adaptors can be used for Ball Valves of water supply downtake branch pipes in toilet & kitchen shaft. Union shall be provided near all ball valves. Brass Insert (male / female) adaptors shall be used for Ball Valves of before & after PRV. Union shall be provided near all ball valves.	960	NOS	334.75	321,360.00	
				CGST Inv(9.00%)	INR	28,922.40
				SGST-Inv(9.00%)	INR	28,922.40
(110)	Sac : 995462 - Inst of 15mm dia ball valve	960	NOS	103.00	98,880.00	

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	8,899.20
				SGST-Inv(9.00%)	INR	8,899.20
(111)	Sac : 995462 - T&C of 15mm dia ball valve	960	NOS	51.50	49,440.00	
				CGST Inv(9.00%)	INR	4,449.60
				SGST-Inv(9.00%)	INR	4,449.60
(112)	Sac : 995462 - Handover of 15mm dia ball valve	960	NOS	25.75	24,720.00	
				CGST Inv(9.00%)	INR	2,224.80
				SGST-Inv(9.00%)	INR	2,224.80
(113)	Sac : 995462 - Supply of 20mm dia ball valve	50	NOS	448.50	22,425.00	
				CGST Inv(9.00%)	INR	2,018.25
				SGST-Inv(9.00%)	INR	2,018.25
(114)	Sac : 995462 - Inst of 20mm dia ball valve	50	NOS	138.00	6,900.00	
				CGST Inv(9.00%)	INR	621.00
				SGST-Inv(9.00%)	INR	621.00
(115)	Sac : 995462 - T&C of 20mm dia ball valve	50	NOS	69.00	3,450.00	
				CGST Inv(9.00%)	INR	310.50
				SGST-Inv(9.00%)	INR	310.50
(116)	Sac : 995462 - Handover of 20mm dia ball valve	50	NOS	34.50	1,725.00	
				CGST Inv(9.00%)	INR	155.25
				SGST-Inv(9.00%)	INR	155.25
(117)	Sac : 995462 - Supply of 25mm dia ball valve	228	NOS	648.70	147,903.60	
				CGST Inv(9.00%)	INR	13,311.32
				SGST-Inv(9.00%)	INR	13,311.32
(118)	Sac : 995462 - Inst of 25mm dia ball valve	228	NOS	199.60	45,508.80	
				CGST Inv(9.00%)	INR	4,095.79
				SGST-Inv(9.00%)	INR	4,095.79
(119)	Sac : 995462 - T&C of 25mm dia ball valve	228	NOS	99.80	22,754.40	
				CGST Inv(9.00%)	INR	2,047.90
				SGST-Inv(9.00%)	INR	2,047.90
(120)	Sac : 995462 - Handover of 25mm dia ball valve	228	NOS	49.90	11,377.20	

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	1,023.95
				SGST-Inv(9.00%)	INR	1,023.95
(121)	Sac : 995462 - Supply of 32mm dia ball valve	174	NOS	1,025.70	178,471.80	
				CGST Inv(9.00%)	INR	16,062.46
				SGST-Inv(9.00%)	INR	16,062.46
(122)	Sac : 995462 - Inst of 32mm dia ball valve	174	NOS	315.60	54,914.40	
				CGST Inv(9.00%)	INR	4,942.30
				SGST-Inv(9.00%)	INR	4,942.30
(123)	Sac : 995462 - T&C of 32mm dia ball valve	174	NOS	157.80	27,457.20	
				CGST Inv(9.00%)	INR	2,471.15
				SGST-Inv(9.00%)	INR	2,471.15
(124)	Sac : 995462 - Handover of 32mm dia ball valve	174	NOS	78.90	13,728.60	
				CGST Inv(9.00%)	INR	1,235.57
				SGST-Inv(9.00%)	INR	1,235.57
(125)	Sac : 995462 - Supply of 40mm dia ball valve	18	NOS	1,478.75	26,617.50	
				CGST Inv(9.00%)	INR	2,395.58
				SGST-Inv(9.00%)	INR	2,395.58
(126)	Sac : 995462 - Inst of 40mm dia ball valve	18	NOS	455.00	8,190.00	
				CGST Inv(9.00%)	INR	737.10
				SGST-Inv(9.00%)	INR	737.10
(127)	Sac : 995462 - T&C of 40mm dia ball valve	18	NOS	227.50	4,095.00	
				CGST Inv(9.00%)	INR	368.55
				SGST-Inv(9.00%)	INR	368.55
(128)	Sac : 995462 - Handover of 40mm dia ball valve	18	NOS	113.75	2,047.50	
				CGST Inv(9.00%)	INR	184.28
				SGST-Inv(9.00%)	INR	184.28
(129)	Sac : 995462 - Supply of 50mm dia ball valve	31	NOS	2,208.70	68,469.70	
				CGST Inv(9.00%)	INR	6,162.27
				SGST-Inv(9.00%)	INR	6,162.27
(130)	Sac : 995462 - Inst of 50mm dia ball valve	31	NOS	679.60	21,067.60	

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	1,896.08
				SGST-Inv(9.00%)	INR	1,896.08
(131)	Sac : 995462 - T&C of 50mm dia ball valve	31	NOS	339.80		10,533.80
				CGST Inv(9.00%)	INR	948.04
				SGST-Inv(9.00%)	INR	948.04
(132)	Sac : 995462 - Handover of 50mm dia ball valve	31	NOS	169.90		5,266.90
				CGST Inv(9.00%)	INR	474.02
				SGST-Inv(9.00%)	INR	474.02
(133)	Sac : 995462 - Supply of 65mm dia ball valve	2	NOS	4,940.00		9,880.00
				CGST Inv(9.00%)	INR	889.20
				SGST-Inv(9.00%)	INR	889.20
(134)	Sac : 995462 - Inst of 65mm dia ball valve	2	NOS	1,520.00		3,040.00
				CGST Inv(9.00%)	INR	273.60
				SGST-Inv(9.00%)	INR	273.60
(135)	Sac : 995462 - T&C of 65mm dia ball valve	2	NOS	760.00		1,520.00
				CGST Inv(9.00%)	INR	136.80
				SGST-Inv(9.00%)	INR	136.80
(136)	Sac : 995462 - Handover of 65mm dia ball valve	2	NOS	380.00		760.00
				CGST Inv(9.00%)	INR	68.40
				SGST-Inv(9.00%)	INR	68.40
(137)	Sac : 995462 - Supply of 80mm dia ball valve	2	NOS	5,848.05		11,696.10
				CGST Inv(9.00%)	INR	1,052.65
				SGST-Inv(9.00%)	INR	1,052.65
(138)	Sac : 995462 - Inst of 80mm dia ball valve	2	NOS	1,799.40		3,598.80
				CGST Inv(9.00%)	INR	323.89
				SGST-Inv(9.00%)	INR	323.89
(139)	Sac : 995462 - T&C of 80mm dia ball valve	2	NOS	899.70		1,799.40
				CGST Inv(9.00%)	INR	161.95
				SGST-Inv(9.00%)	INR	161.95
(140)	Sac : 995462 - Handover of 80mm dia ball valve	2	NOS	449.85		899.70

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	80.97
				SGST-Inv(9.00%)	INR	80.97
(141)	Sac : 995462 - Supply of 50mm dia butterfly valve PN-16 Providing & fixing butterfly valve (upto 150mm dia with hand lever operation & above with gear box operation). Tested to a pressure not less than as mentioned below, Including rubber gasket, G.I. flanges, G.I. nuts, G.I. bolts, G.I. washers. For tank interconnection, pump suction / delivery, STP, bore well, Tanker inlet, Sump Pump, RWH lines etc.	5	NOS	2,080.00	10,400.00	
				CGST Inv(9.00%)	INR	936.00
				SGST-Inv(9.00%)	INR	936.00
(142)	Sac : 995462 - Inst of 50mm dia butterfly valve PN-16	5	NOS	640.00	3,200.00	
				CGST Inv(9.00%)	INR	288.00
				SGST-Inv(9.00%)	INR	288.00
(143)	Sac : 995462 - T&C of 50mm dia butterfly valve PN-16	5	NOS	320.00	1,600.00	
				CGST Inv(9.00%)	INR	144.00
				SGST-Inv(9.00%)	INR	144.00
(144)	Sac : 995462 - Handover of 50mm dia butterfly valve PN-	5	NOS	160.00	800.00	
				CGST Inv(9.00%)	INR	72.00
				SGST-Inv(9.00%)	INR	72.00
(145)	Sac : 995462 - Supply of 80mm dia butterfly valve PN-10	17	NOS	2,208.70	37,547.90	
				CGST Inv(9.00%)	INR	3,379.31
				SGST-Inv(9.00%)	INR	3,379.31
(146)	Sac : 995462 - Inst of 80mm dia butterfly valve PN-10	17	NOS	679.60	11,553.20	
				CGST Inv(9.00%)	INR	1,039.79
				SGST-Inv(9.00%)	INR	1,039.79
(147)	Sac : 995462 - T&C of 80mm dia butterfly valve PN-10	17	NOS	339.80	5,776.60	
				CGST Inv(9.00%)	INR	519.89
				SGST-Inv(9.00%)	INR	519.89

Corporate Addr.:514, Dalmal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
(148)	Sac : 995462 - Handover of 80mm dia butterfly valve PN-	17	NOS	169.90	2,888.30	
				CGST Inv(9.00%)	INR	259.95
				SGST-Inv(9.00%)	INR	259.95
(149)	Sac : 995462 - Supply of 80mm dia butterfly valve PN-16	5	NOS	2,325.70	11,628.50	
				CGST Inv(9.00%)	INR	1,046.57
				SGST-Inv(9.00%)	INR	1,046.57
(150)	Sac : 995462 - Inst of 80mm dia butterfly valve PN-16	5	NOS	715.60	3,578.00	
				CGST Inv(9.00%)	INR	322.02
				SGST-Inv(9.00%)	INR	322.02
(151)	Sac : 995462 - T&C of 80mm dia butterfly valve PN-16	5	NOS	357.80	1,789.00	
				CGST Inv(9.00%)	INR	161.01
				SGST-Inv(9.00%)	INR	161.01
(152)	Sac : 995462 - Handover of 80mm dia butterfly valve PN-	5	NOS	178.90	894.50	
				CGST Inv(9.00%)	INR	80.51
				SGST-Inv(9.00%)	INR	80.51
(153)	Sac : 995462 - Supply of 100mm dia butterfly valve PN-1	9	NOS	2,964.65	26,681.85	
				CGST Inv(9.00%)	INR	2,401.37
				SGST-Inv(9.00%)	INR	2,401.37
(154)	Sac : 995462 - Inst of 100mm dia butterfly valve PN-10	9	NOS	912.20	8,209.80	
				CGST Inv(9.00%)	INR	738.88
				SGST-Inv(9.00%)	INR	738.88
(155)	Sac : 995462 - T&C of 100mm dia butterfly valve PN-10	9	NOS	456.10	4,104.90	
				CGST Inv(9.00%)	INR	369.44
				SGST-Inv(9.00%)	INR	369.44
(156)	Sac : 995462 - Handover of 100mm dia butterfly valve PN	9	NOS	228.05	2,052.45	
				CGST Inv(9.00%)	INR	184.72
				SGST-Inv(9.00%)	INR	184.72

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
(157)	Sac : 995462 - Supply of 150mm dia butterfly valve PN-1	2	NOS	4,819.75	9,639.50	
				CGST Inv(9.00%)	INR	867.56
				SGST-Inv(9.00%)	INR	867.56
(158)	Sac : 995462 - Inst of 150mm dia butterfly valve PN-10	2	NOS	1,483.00	2,966.00	
				CGST Inv(9.00%)	INR	266.94
				SGST-Inv(9.00%)	INR	266.94
(159)	Sac : 995462 - T&C of 150mm dia butterfly valve PN-10	2	NOS	741.50	1,483.00	
				CGST Inv(9.00%)	INR	133.47
				SGST-Inv(9.00%)	INR	133.47
(160)	Sac : 995462 - Handover of 150mm dia butterfly valve PN	2	NOS	370.75	741.50	
				CGST Inv(9.00%)	INR	66.74
				SGST-Inv(9.00%)	INR	66.74
(161)	Sac : 995462 - Supply of 25mm dia PRV Providing, fixing, testing and commissioning of PRV in water supply downtime / branch pipes. To be installed inside shaft, on-line type. Additional supports shall be provided to PRV as per site condition. Brass insert (male / female) adaptors shall be used for all PRV's. Also 'Tee' used before & after PRV for pressure gauge shall be brass insert type.	92	NOS	2,982.20	274,362.40	
				CGST Inv(9.00%)	INR	24,692.62
				SGST-Inv(9.00%)	INR	24,692.62
(162)	Sac : 995462 - Inst of 25mm dia PRV	92	NOS	917.60	84,419.20	
				CGST Inv(9.00%)	INR	7,597.73
				SGST-Inv(9.00%)	INR	7,597.73
(163)	Sac : 995462 - T&C of 25mm dia PRV	92	NOS	458.80	42,209.60	
				CGST Inv(9.00%)	INR	3,798.86
				SGST-Inv(9.00%)	INR	3,798.86
(164)	Sac : 995462 - Handover of 25mm dia PRV	92	NOS	229.40	21,104.80	
				CGST Inv(9.00%)	INR	1,899.43
				SGST-Inv(9.00%)	INR	1,899.43

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
(165)	Sac : 995462 - Supply of 32mm dia PRV	68	NOS	3,642.60	247,696.80	
				CGST Inv(9.00%)	INR	22,292.71
				SGST-Inv(9.00%)	INR	22,292.71
(166)	Sac : 995462 - Inst of 32mm dia PRV	68	NOS	1,120.80	76,214.40	
				CGST Inv(9.00%)	INR	6,859.30
				SGST-Inv(9.00%)	INR	6,859.30
(167)	Sac : 995462 - T&C of 32mm dia PRV	68	NOS	560.40	38,107.20	
				CGST Inv(9.00%)	INR	3,429.65
				SGST-Inv(9.00%)	INR	3,429.65
(168)	Sac : 995462 - Handover of 32mm dia PRV	68	NOS	280.20	19,053.60	
				CGST Inv(9.00%)	INR	1,714.82
				SGST-Inv(9.00%)	INR	1,714.82
(169)	Sac : 995462 - Supply of 25mm dia Water meter Providing, fixing, testing and commissioning water meter with direct reading dial in KL with all integral parts of gun metal or brass with necessary fitting such as threaded pieces, unions pressure gauge and isolation cock, flanges piece for future removal, flanges / unions complete with all necessary testing charges and obtaining test certificates from municipal authorities, on following size pipe lines. (Municipal water , STP, Bore well & DCB lines). (ball valve & strainer considered in respective item)	1	NOS	2,943.85	2,943.85	
				CGST Inv(9.00%)	INR	264.95
				SGST-Inv(9.00%)	INR	264.95
(170)	Sac : 995462 - Inst of 25mm dia Water meter	1	NOS	905.80	905.80	
				CGST Inv(9.00%)	INR	81.52
				SGST-Inv(9.00%)	INR	81.52
(171)	Sac : 995462 - T&C of 25mm dia Water meter	1	NOS	452.90	452.90	
				CGST Inv(9.00%)	INR	40.76
				SGST-Inv(9.00%)	INR	40.76
(172)	Sac : 995462 - Handover of 25mm dia Water meter	1	NOS	226.45	226.45	
				CGST Inv(9.00%)	INR	20.38
				SGST-Inv(9.00%)	INR	20.38

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value
(173)	Sac : 995462 - Supply of 50mm dia Water meter	2	NOS	7,148.70 CGST Inv(9.00%) SGST-Inv(9.00%)	14,297.40 INR 1,286.77 INR 1,286.77
(174)	Sac : 995462 - Inst of 50mm dia Water meter	2	NOS	2,199.60 CGST Inv(9.00%) SGST-Inv(9.00%)	4,399.20 INR 395.93 INR 395.93
(175)	Sac : 995462 - T&C of 50mm dia Water meter	2	NOS	1,099.80 CGST Inv(9.00%) SGST-Inv(9.00%)	2,199.60 INR 197.96 INR 197.96
(176)	Sac : 995462 - Handover of 50mm dia Water meter	2	NOS	549.90 CGST Inv(9.00%) SGST-Inv(9.00%)	1,099.80 INR 98.98 INR 98.98
(177)	Sac : 995462 - Supply of 80mm dia Water meter	1	NOS	8,728.20 CGST Inv(9.00%) SGST-Inv(9.00%)	8,728.20 INR 785.54 INR 785.54
(178)	Sac : 995462 - Inst of 80mm dia Water meter	1	NOS	2,685.60 CGST Inv(9.00%) SGST-Inv(9.00%)	2,685.60 INR 241.70 INR 241.70
(179)	Sac : 995462 - T&C of 80mm dia Water meter	1	NOS	1,342.80 CGST Inv(9.00%) SGST-Inv(9.00%)	1,342.80 INR 120.85 INR 120.85
(180)	Sac : 995462 - Handover of 80mm dia Water meter	1	NOS	671.40 CGST Inv(9.00%) SGST-Inv(9.00%)	671.40 INR 60.43 INR 60.43
(181)	Sac : 995462 - Supply of 15mm dia Auto Air vent Providing & fixing Auto Air vent for cold water supply risers, suitable for pressure not less than 15 Kg/Sq.cm. (For top 3 floor loop).	8	NOS	326.95 CGST Inv(9.00%) SGST-Inv(9.00%)	2,615.60 INR 235.40 INR 235.40
(182)	Sac : 995462 - Inst of 15mm dia Auto Air vent	8	NOS	100.60	804.80

Corporate Addr.:514, Dalmal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	72.43
				SGST-Inv(9.00%)	INR	72.43
(183)	Sac : 995462 - T&C of 15mm dia Auto Air vent	8	NOS	50.30	402.40	
				CGST Inv(9.00%)	INR	36.22
				SGST-Inv(9.00%)	INR	36.22
(184)	Sac : 995462 - Handover of 15mm dia Auto Air vent	8	NOS	25.15	201.20	
				CGST Inv(9.00%)	INR	18.11
				SGST-Inv(9.00%)	INR	18.11
(185)	Sac : 995462 - Supply of 65mm(PN-16) dia Non Return val	3	NOS	1,807.00	5,421.00	
				CGST Inv(9.00%)	INR	487.89
				SGST-Inv(9.00%)	INR	487.89
(186)	Sac : 995462 - Inst of 65mm(PN-16) dia Non Return valve	3	NOS	556.00	1,668.00	
				CGST Inv(9.00%)	INR	150.12
				SGST-Inv(9.00%)	INR	150.12
(187)	Sac : 995462 - T&C of 65mm(PN-16) dia Non Return valves	3	NOS	278.00	834.00	
				CGST Inv(9.00%)	INR	75.06
				SGST-Inv(9.00%)	INR	75.06
(188)	Sac : 995462 - Handover of 65mm(PN-16) dia Non Return v	3	NOS	139.00	417.00	
				CGST Inv(9.00%)	INR	37.53
				SGST-Inv(9.00%)	INR	37.53
(189)	Sac : 995462 - Supply of 80mm(PN-10) dia Non Return val	2	NOS	1,592.50	3,185.00	
				CGST Inv(9.00%)	INR	286.65
				SGST-Inv(9.00%)	INR	286.65
(190)	Sac : 995462 - Inst of 80mm(PN-10) dia Non Return valve	2	NOS	490.00	980.00	
				CGST Inv(9.00%)	INR	88.20
				SGST-Inv(9.00%)	INR	88.20

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
(191)	Sac : 995462 - T&C of 80mm(PN-10) dia Non Return valves	2	NOS	245.00		490.00
				CGST Inv(9.00%)	INR	44.10
				SGST-Inv(9.00%)	INR	44.10
(192)	Sac : 995462 - Handover of 80mm(PN-10) dia Non Return v	2	NOS	122.50		245.00
				CGST Inv(9.00%)	INR	22.05
				SGST-Inv(9.00%)	INR	22.05
(193)	Sac : 995462 - Supply of 80mm(PN-16) dia Non Return val Providing & fixing of heavy quality Non Return valves of gun metal / brass / CI body with screwed / flanged ends pressure as mentioned below & as per details mentioned in approved materials list etc. complete (For plant room, sump pump, etc.) Flanged end - Dual plate type.	3	NOS	1,792.70		5,378.10
				CGST Inv(9.00%)	INR	484.03
				SGST-Inv(9.00%)	INR	484.03
(194)	Sac : 995462 - Inst of 80mm(PN-16) dia Non Return valve	3	NOS	551.60		1,654.80
				CGST Inv(9.00%)	INR	148.93
				SGST-Inv(9.00%)	INR	148.93
(195)	Sac : 995462 - T&C of 80mm(PN-16) dia Non Return valves	3	NOS	275.80		827.40
				CGST Inv(9.00%)	INR	74.47
				SGST-Inv(9.00%)	INR	74.47
(196)	Sac : 995462 - Handover of 80mm(PN-16) dia Non Return v	3	NOS	137.90		413.70
				CGST Inv(9.00%)	INR	37.23
				SGST-Inv(9.00%)	INR	37.23
(197)	Sac : 995462 - Supply of 100mm(PN-10) dia Non Return va	2	NOS	4,550.00		9,100.00
				CGST Inv(9.00%)	INR	819.00
				SGST-Inv(9.00%)	INR	819.00
(198)	Sac : 995462 - Inst of 100mm(PN-10) dia Non Return valv	2	NOS	1,400.00		2,800.00

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	252.00
				SGST-Inv(9.00%)	INR	252.00
(199)	Sac : 995462 - T&C of 100mm(PN-10) dia Non Return valve	2	NOS	700.00		1,400.00
				CGST Inv(9.00%)	INR	126.00
				SGST-Inv(9.00%)	INR	126.00
(200)	Sac : 995462 - Handover of 100mm(PN-10) dia Non Return	2	NOS	350.00		700.00
				CGST Inv(9.00%)	INR	63.00
				SGST-Inv(9.00%)	INR	63.00
(201)	Sac : 995462 - Supply of 25mm dia Y Type Strainer Providing & fixing of heavy quality Strainers (with 400 micron SS mesh) of gun metal / brass / CI body with screwed / flanged ends 16kg class as per details mentioned in approved materials list etc. complete (For Terrace Loop, Water meter etc.). CI body Strainers with anti corrosive coating. Including rubber gasket, G.I. flanges, G.I. nuts, G.I. bolts, G.I. washers for flanged end strainers.	1	NOS	487.50		487.50
				CGST Inv(9.00%)	INR	43.88
				SGST-Inv(9.00%)	INR	43.88
(202)	Sac : 995462 - Inst of 25mm dia Y Type Strainer	1	NOS	150.00		150.00
				CGST Inv(9.00%)	INR	13.50
				SGST-Inv(9.00%)	INR	13.50
(203)	Sac : 995462 - T&C of 25mm dia Y Type Strainer	1	NOS	75.00		75.00
				CGST Inv(9.00%)	INR	6.75
				SGST-Inv(9.00%)	INR	6.75
(204)	Sac : 995462 - Handover of 25mm dia Y Type Strainer	1	NOS	37.50		37.50
				CGST Inv(9.00%)	INR	3.38
				SGST-Inv(9.00%)	INR	3.38
(205)	Sac : 995462 - Supply of 50mm dia Y Type Strainer	2	NOS	1,571.70		3,143.40
				CGST Inv(9.00%)	INR	282.91
				SGST-Inv(9.00%)	INR	282.91
(206)	Sac : 995462 - Inst of 50mm dia Y Type Strainer	2	NOS	483.60		967.20

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	87.05
				SGST-Inv(9.00%)	INR	87.05
(207)	Sac : 995462 - T&C of 50mm dia Y Type Strainer	2	NOS	241.80	483.60	
				CGST Inv(9.00%)	INR	43.52
				SGST-Inv(9.00%)	INR	43.52
(208)	Sac : 995462 - Handover of 50mm dia Y Type Strainer	2	NOS	120.90	241.80	
				CGST Inv(9.00%)	INR	21.76
				SGST-Inv(9.00%)	INR	21.76
(209)	Sac : 995462 - Supply of 65mm dia Y Type Strainer	2	NOS	6,916.65	13,833.30	
				CGST Inv(9.00%)	INR	1,245.00
				SGST-Inv(9.00%)	INR	1,245.00
(210)	Sac : 995462 - Inst of 65mm dia Y Type Strainer	2	NOS	2,128.20	4,256.40	
				CGST Inv(9.00%)	INR	383.08
				SGST-Inv(9.00%)	INR	383.08
(211)	Sac : 995462 - T&C of 65mm dia Y Type Strainer	2	NOS	1,064.10	2,128.20	
				CGST Inv(9.00%)	INR	191.54
				SGST-Inv(9.00%)	INR	191.54
(212)	Sac : 995462 - Handover of 65mm dia Y Type Strainer	2	NOS	532.05	1,064.10	
				CGST Inv(9.00%)	INR	95.77
				SGST-Inv(9.00%)	INR	95.77
(213)	Sac : 995462 - Supply of 80mm dia Y Type Strainer	2	NOS	8,747.05	17,494.10	
				CGST Inv(9.00%)	INR	1,574.47
				SGST-Inv(9.00%)	INR	1,574.47
(214)	Sac : 995462 - Inst of 80mm dia Y Type Strainer	2	NOS	2,691.40	5,382.80	
				CGST Inv(9.00%)	INR	484.45
				SGST-Inv(9.00%)	INR	484.45
(215)	Sac : 995462 - T&C of 80mm dia Y Type Strainer	2	NOS	1,345.70	2,691.40	
				CGST Inv(9.00%)	INR	242.23
				SGST-Inv(9.00%)	INR	242.23
(216)	Sac : 995462 - Handover of 80mm dia Y Type Strainer	2	NOS	672.85	1,345.70	

Corporate Addr.:514, Dalmal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	121.11
				SGST-Inv(9.00%)	INR	121.11
(217)	Sac : 995462 - Supply of 65mm dia Y Type Strainer	2	NOS	3,737.50	7,475.00	
				CGST Inv(9.00%)	INR	672.75
				SGST-Inv(9.00%)	INR	672.75
(218)	Sac : 995462 - Inst of 65mm dia Y Type Strainer	2	NOS	1,150.00	2,300.00	
				CGST Inv(9.00%)	INR	207.00
				SGST-Inv(9.00%)	INR	207.00
(219)	Sac : 995462 - T&C of 65mm dia Y Type Strainer	2	NOS	575.00	1,150.00	
				CGST Inv(9.00%)	INR	103.50
				SGST-Inv(9.00%)	INR	103.50
(220)	Sac : 995462 - Handover of 65mm dia Y Type Strainer	2	NOS	287.50	575.00	
				CGST Inv(9.00%)	INR	51.75
				SGST-Inv(9.00%)	INR	51.75
(221)	Sac : 995462 - Supply of 80mm dia Y Type Strainer	3	NOS	3,890.90	11,672.70	
				CGST Inv(9.00%)	INR	1,050.54
				SGST-Inv(9.00%)	INR	1,050.54
(222)	Sac : 995462 - Inst of 80mm dia Y Type Strainer	3	NOS	1,197.20	3,591.60	
				CGST Inv(9.00%)	INR	323.24
				SGST-Inv(9.00%)	INR	323.24
(223)	Sac : 995462 - T&C of 80mm dia Y Type Strainer	3	NOS	598.60	1,795.80	
				CGST Inv(9.00%)	INR	161.62
				SGST-Inv(9.00%)	INR	161.62
(224)	Sac : 995462 - Handover of 80mm dia Y Type Strainer	3	NOS	299.30	897.90	
				CGST Inv(9.00%)	INR	80.81
				SGST-Inv(9.00%)	INR	80.81
(225)	Sac : 995462 - Supply of 100mm dia Y Type Strainer	5	NOS	5,523.70	27,618.50	
				CGST Inv(9.00%)	INR	2,485.67
				SGST-Inv(9.00%)	INR	2,485.67
(226)	Sac : 995462 - Inst of 100mm dia Y Type Strainer	5	NOS	1,699.60	8,498.00	

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	764.82
				SGST-Inv(9.00%)	INR	764.82
(227)	Sac : 995462 - T&C of 100mm dia Y Type Strainer	5	NOS	849.80	4,249.00	
				CGST Inv(9.00%)	INR	382.41
				SGST-Inv(9.00%)	INR	382.41
(228)	Sac : 995462 - Handover of 100mm dia Y Type Strainer	5	NOS	424.90	2,124.50	
				CGST Inv(9.00%)	INR	191.21
				SGST-Inv(9.00%)	INR	191.21
(229)	Sac : 995462 - Supply of water tank circular cover Providing and fixing 600 mm dia cast iron (heavy duty) water tank circular cover with frame 40 mm CI seat & lockable arrangement complete in all regards (Total WT of cover and frame to be not less than 20.8 kg). Including painting with 3 coats of bitumastic paint. (All UG & OH tanks).	15	NOS	2,778.75	41,681.25	
				CGST Inv(9.00%)	INR	3,751.31
				SGST-Inv(9.00%)	INR	3,751.31
(230)	Sac : 995462 - Inst of water tank circular cover	15	NOS	855.00	12,825.00	
				CGST Inv(9.00%)	INR	1,154.25
				SGST-Inv(9.00%)	INR	1,154.25
(231)	Sac : 995462 - T&C of water tank circular cover	15	NOS	427.50	6,412.50	
				CGST Inv(9.00%)	INR	577.13
				SGST-Inv(9.00%)	INR	577.13
(232)	Sac : 995462 - Handover of water tank circular cover	15	NOS	213.75	3,206.25	
				CGST Inv(9.00%)	INR	288.56
				SGST-Inv(9.00%)	INR	288.56

Corporate Addr.:514, Dalmal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value
(233)	Sac : 995462 - P&C of block masonry chamber Size 900 Providing & Constructing of block masonry chamber (for housing valves, Meters etc.) of block work with cement mortar 1:5 (1 cement:5 fine sand) plastering internal face with cement mortar 1:3 (1 cement: 3 fine sand and rough plaster on outer face with a floating coat of neat cement with required duty Ductile Iron manhole cover and frame with locking arrangement, Including excavation, dewatering, refilling, watering, ramming and removing the surplus excavated material complete as required. (All sizes are clear internal sizes).	2	NOS	27,800.00	55,600.00
				CGST Inv(9.00%)	INR 5,004.00
				SGST-Inv(9.00%)	INR 5,004.00
(234)	Sac : 995462 - Supply of 50mm Vent pipe Providing & fixing of vapour vent pipes of 50mm with GI Tee, Elbow, Pvc Mosquito proof jali including required jointing material etc. complete. (1 set = 2" pipex300mm + 1 Coupling + 1 Tee + 2 Elbow + 2 mosquito jali).	24	NOS	503.75	12,090.00
				CGST Inv(9.00%)	INR 1,088.10
				SGST-Inv(9.00%)	INR 1,088.10
(235)	Sac : 995462 - Inst of 50mm Vent pipe	24	NOS	155.00	3,720.00
				CGST Inv(9.00%)	INR 334.80
				SGST-Inv(9.00%)	INR 334.80
(236)	Sac : 995462 - T&C of 50mm Vent pipe	24	NOS	77.50	1,860.00
				CGST Inv(9.00%)	INR 167.40
				SGST-Inv(9.00%)	INR 167.40
(237)	Sac : 995462 - Handover of 50mm Vent pipe	24	NOS	38.75	930.00
				CGST Inv(9.00%)	INR 83.70
				SGST-Inv(9.00%)	INR 83.70
Corporate Addr.:514, Dalomal Tower, 211 FPJ Marg,Nariman Point, Mumbai- 400021, Tel No.					
Page No. : 32 / 88 -> 4700157988					

Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value
(238)	Sac : 995462 - Supply of dial type pressure gauge Providing, fixing, jointing and testing in position approved quality of dial type pressure gauge with glycerin filled S.S. Bourdon tube pressure scale of 0 to 10 / 15 / 25 kg / cm ² . Application areas (activity) - A) Pump room delivery lines (flushing / domestic) B) Downtake PRV setting (4 gauges min.) C) For Terrace Booster system. Calibration shall be done for pressure gauges and certificate shall be submitted before starting of pressure testing works for any plumbing lines and for pressure gauges for pump rooms. (as per requirement of ISO) With below details - a) Make of gauge - b) Pressure Range of gauge - c) Date of calibration - d) Calibration DUE on -	12	NOS	778.70	9,344.40
				CGST Inv(9.00%)	INR 841.00
				SGST-Inv(9.00%)	INR 841.00
(239)	Sac : 995462 - Inst of dial type pressure gauge	12	NOS	239.60	2,875.20
				CGST Inv(9.00%)	INR 258.77
				SGST-Inv(9.00%)	INR 258.77
(240)	Sac : 995462 - T&C of dial type pressure gauge	12	NOS	119.80	1,437.60
				CGST Inv(9.00%)	INR 129.38
				SGST-Inv(9.00%)	INR 129.38
(241)	Sac : 995462 - Handover of dial type pressure gauge	12	NOS	59.90	718.80
				CGST Inv(9.00%)	INR 64.69
				SGST-Inv(9.00%)	INR 64.69
(242)	Sac : 995462 - Supply of 65mm rubber expansion joint Providing, fixing, jointing and testing in position double flanged flexicon rubber expansion joint for Domestic & Flushing pump delivery lines + between third NRV & Butterfly valve (suitable for system test pressure) of standard length as per manufacturers specs including rubber gaskets, GI flanges, GI nuts, bolts and washers complete as required. PN-16	3	NOS	3,217.50	9,652.50
				CGST Inv(9.00%)	INR 868.73
				SGST-Inv(9.00%)	INR 868.73
(243)	Sac : 995462 - Inst of 65mm rubber expansion joint	3	NOS	990.00	2,970.00
Corporate Addr.:514, Dalalal Tower, 211 FPJ Marg,Nariman Point, Mumbai- 400021, Tel No.					
Page No. : 33 / 38 -> 4700157988					
					

Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	267.30
				SGST-Inv(9.00%)	INR	267.30
(244)	Sac : 995462 - T&C of 65mm rubber expansion joint	3	NOS	495.00		1,485.00
				CGST Inv(9.00%)	INR	133.65
				SGST-Inv(9.00%)	INR	133.65
(245)	Sac : 995462 - Handover of 65mm rubber expansion joint	3	NOS	247.50		742.50
				CGST Inv(9.00%)	INR	66.83
				SGST-Inv(9.00%)	INR	66.83
(246)	Sac : 995462 - Supply of 80mm rubber expansion joint	3	NOS	3,932.50		11,797.50
				CGST Inv(9.00%)	INR	1,061.78
				SGST-Inv(9.00%)	INR	1,061.78
(247)	Sac : 995462 - Inst of 80mm rubber expansion joint	3	NOS	1,210.00		3,630.00
				CGST Inv(9.00%)	INR	326.70
				SGST-Inv(9.00%)	INR	326.70
(248)	Sac : 995462 - T&C of 80mm rubber expansion joint	3	NOS	605.00		1,815.00
				CGST Inv(9.00%)	INR	163.35
				SGST-Inv(9.00%)	INR	163.35
(249)	Sac : 995462 - Handover of 80mm rubber expansion joint	3	NOS	302.50		907.50
				CGST Inv(9.00%)	INR	81.68
				SGST-Inv(9.00%)	INR	81.68
(250)	Sac : 995462 - Supply of 100mm rubber expansion joint	2	NOS	4,550.00		9,100.00
				CGST Inv(9.00%)	INR	819.00
				SGST-Inv(9.00%)	INR	819.00
(251)	Sac : 995462 - Inst of 100mm rubber expansion joint	2	NOS	1,400.00		2,800.00
				CGST Inv(9.00%)	INR	252.00
				SGST-Inv(9.00%)	INR	252.00
(252)	Sac : 995462 - T&C of 100mm rubber expansion joint	2	NOS	700.00		1,400.00
				CGST Inv(9.00%)	INR	126.00

Corporate Addr.:514, Dalmal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				SGST-Inv(9.00%)	INR	126.00
(253)	Sac : 995462 - Handover of 100mm rubber expansion joint	2	NOS	350.00	INR	700.00
				CGST Inv(9.00%)	INR	63.00
				SGST-Inv(9.00%)	INR	63.00
(254)	Sac : 995462 - Supply of 160mm UPVC Pipe Type A INTERNAL DRAINAGE (SOIL, WASTE & VENT)	325	M	536.25	174,281.25	
	Providing, fixing, jointing, testing and commissioning of UPVC pipe Type-A for R.W. upto 160mm dia. confirming to IS 13592 & AGRI for R.W. above 160 mm dia confirming to IS:4985 cut to required lengths including all necessary fittings and specials such as 45 or 90 deg. bends, Tee's, Y's, access pipe with solvent cement jointing. Fixing at wall / ceiling level supported by galvanized brackets & pvc coated clamps & hangers etc. All pipe diversions shall be done with 45 degree bends where ever required due to beam offsets or cutout changes at any level. For vertical support, fix 4 brackets/floor or 1 m c/c whichever is less. For Vertical Rain Water Pipes Scope includes connection of service floor drains to Multiples RWP pipes with using Y' & Bends.			CGST Inv(9.00%)	INR	15,685.31
				SGST-Inv(9.00%)	INR	15,685.31
(255)	Sac : 995462 - Inst of 160mm UPVC Pipe Type A	325	M	165.00	53,625.00	
				CGST Inv(9.00%)	INR	4,826.25
				SGST-Inv(9.00%)	INR	4,826.25
(256)	Sac : 995462 - T&C of 160mm UPVC Pipe Type A	325	M	82.50	26,812.50	
				CGST Inv(9.00%)	INR	2,413.13
				SGST-Inv(9.00%)	INR	2,413.13
(257)	Sac : 995462 - Handover of 160mm UPVC Pipe Type A	325	M	41.25	13,406.25	
				CGST Inv(9.00%)	INR	1,206.56
				SGST-Inv(9.00%)	INR	1,206.56
(258)	Sac : 995462 - Supply of 110mm UPVC Pipe Type A	350	M	292.50	102,375.00	
				CGST Inv(9.00%)	INR	9,213.75
				SGST-Inv(9.00%)	INR	9,213.75
Corporate Addr.:514, Dalalal Tower, 211 FPJ Marg,Nariman Point, Mumbai- 400021, Tel No.						
Page No. : 35 / 88 -> 4700157988						



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
(259)	Sac : 995462 - Inst of 110mm UPVC Pipe Type A	350	M	90.00	31,500.00	
				CGST Inv(9.00%)	INR	2,835.00
				SGST-Inv(9.00%)	INR	2,835.00
(260)	Sac : 995462 - T&C of 110mm UPVC Pipe Type A	350	M	45.00	15,750.00	
				CGST Inv(9.00%)	INR	1,417.50
				SGST-Inv(9.00%)	INR	1,417.50
(261)	Sac : 995462 - Handover of 110mm UPVC Pipe Type A	350	M	22.50	7,875.00	
				CGST Inv(9.00%)	INR	708.75
				SGST-Inv(9.00%)	INR	708.75
(262)	Sac : 995462 - Supply of 75mm UPVC Pipe Type A	10	M	211.25	2,112.50	
				CGST Inv(9.00%)	INR	190.13
				SGST-Inv(9.00%)	INR	190.13
(263)	Sac : 995462 - Inst of 75mm UPVC Pipe Type A	10	M	65.00	650.00	
				CGST Inv(9.00%)	INR	58.50
				SGST-Inv(9.00%)	INR	58.50
(264)	Sac : 995462 - T&C of 110mm UPVC Pipe Type A	10	M	32.50	325.00	
				CGST Inv(9.00%)	INR	29.25
				SGST-Inv(9.00%)	INR	29.25
(265)	Sac : 995462 - Handover of 110mm UPVC Pipe Type A	10	M	16.25	162.50	
				CGST Inv(9.00%)	INR	14.63
				SGST-Inv(9.00%)	INR	14.63

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value
(266)	Sac : 995462 - Supply of 110mm UPVC Pipe Type B Providing, fixing, jointing, testing and commissioning of UPVC pipe Type-A for vent & Type-B for Soil, Waste & A.C. drains upto 160mm dia. confirming to IS 13592 cut to required lengths including all necessary fittings and specials such as as 45 or 90 deg. bends, Swept Tee's, Y's, access pipe with rubber ring jointing. PVC Cowl on top with solvent joint. Fixing at wall / ceiling level supported by galvanized brackets & PVC coated clamps & hangers etc. Vertical stacks shall be truly vertical & parallel to the wall and supported on M.S. Hot dip Galvanised brackets with PVC coated 'U' clamps, so that the pipes are at least 100mm away from the finished surface/ plaster. Also 75mm to 100mm gap between 2 pipes should be maintained. All pipe diversions shall be done with 45 degree bends where ever required due to beam offsets or cutout changes at any level. For vertical support, fix 3 brackets/floor or 1 m c/c whichever is less. For Vertical Soil, Waste, Vent, Anti Siphonage, AC Drain etc. Only Swept Tee with Door shall be used for all Soil and Waste lines which are with Tee connections shown on drawing.	1,284	M	425.10	545,828.40
(267)	Sac : 995462 - Inst of 110mm UPVC Pipe Type B	1,284	M	130.80	167,947.20
				CGST Inv(9.00%)	INR 49,124.56
				SGST-Inv(9.00%)	INR 49,124.56
(268)	Sac : 995462 - T&C of 110mm UPVC Pipe Type B	1,284	M	65.40	83,973.60
				CGST Inv(9.00%)	INR 7,557.62
				SGST-Inv(9.00%)	INR 7,557.62
(269)	Sac : 995462 - Handover of 110mm UPVC Pipe Type B	1,284	M	32.70	41,986.80
				CGST Inv(9.00%)	INR 3,778.81
				SGST-Inv(9.00%)	INR 3,778.81
(270)	Sac : 995462 - Supply of 75mm UPVC Pipe Type A	1,545	M	229.45	354,500.25
				CGST Inv(9.00%)	INR 31,905.02
				SGST-Inv(9.00%)	INR 31,905.02
(271)	Sac : 995462 - Inst of 75mm UPVC Pipe Type A	1,545	M	70.60	109,077.00

Corporate Addr.:514, Dalmal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	9,816.93
				SGST-Inv(9.00%)	INR	9,816.93
(272)	Sac : 995462 - T&C of 75mm UPVC Pipe Type A	1,545	M	35.30	54,538.50	
				CGST Inv(9.00%)	INR	4,908.47
				SGST-Inv(9.00%)	INR	4,908.47
(273)	Sac : 995462 - Handover of 75mm UPVC Pipe Type A	1,545	M	17.65	27,269.25	
				CGST Inv(9.00%)	INR	2,454.23
				SGST-Inv(9.00%)	INR	2,454.23
(274)	Sac : 995462 - Supply of 75mm UPVC Pipe Type B	1,926	M	306.15	589,644.90	
				CGST Inv(9.00%)	INR	53,068.04
				SGST-Inv(9.00%)	INR	53,068.04
(275)	Sac : 995462 - Inst of 75mm UPVC Pipe Type B	1,926	M	94.20	181,429.20	
				CGST Inv(9.00%)	INR	16,328.63
				SGST-Inv(9.00%)	INR	16,328.63
(276)	Sac : 995462 - T&C of 75mm UPVC Pipe Type B	1,926	M	47.10	90,714.60	
				CGST Inv(9.00%)	INR	8,164.31
				SGST-Inv(9.00%)	INR	8,164.31
(277)	Sac : 995462 - Handover of 75mm UPVC Pipe Type B	1,926	M	23.55	45,357.30	
				CGST Inv(9.00%)	INR	4,082.16
				SGST-Inv(9.00%)	INR	4,082.16
(278)	Sac : 995462 - Supply of 75mm UPVC Pipe Type B	642	M	307.45	197,382.90	
				CGST Inv(9.00%)	INR	17,764.46
				SGST-Inv(9.00%)	INR	17,764.46
(279)	Sac : 995462 - Inst of 75mm UPVC Pipe Type B	642	M	94.60	60,733.20	
				CGST Inv(9.00%)	INR	5,465.99
				SGST-Inv(9.00%)	INR	5,465.99
(280)	Sac : 995462 - T&C of 75mm UPVC Pipe Type B	642	M	47.30	30,366.60	
				CGST Inv(9.00%)	INR	2,732.99
				SGST-Inv(9.00%)	INR	2,732.99
(281)	Sac : 995462 - Handover of 75mm UPVC Pipe Type B	642	M	23.65	15,183.30	

Corporate Addr.:514, Dalmal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	1,366.50
				SGST-Inv(9.00%)	INR	1,366.50
(282)	Sac : 995462 - Supply of 75mm UPVC Pipe Type A	642	M	232.70	149,393.40	
				CGST Inv(9.00%)	INR	13,445.41
				SGST-Inv(9.00%)	INR	13,445.41
(283)	Sac : 995462 - Inst of 75mm UPVC Pipe Type A	642	M	71.60	45,967.20	
				CGST Inv(9.00%)	INR	4,137.05
				SGST-Inv(9.00%)	INR	4,137.05
(284)	Sac : 995462 - T&C of 75mm UPVC Pipe Type A	642	M	35.80	22,983.60	
				CGST Inv(9.00%)	INR	2,068.52
				SGST-Inv(9.00%)	INR	2,068.52
(285)	Sac : 995462 - Handover of 75mm UPVC Pipe Type A	642	M	17.90	11,491.80	
				CGST Inv(9.00%)	INR	1,034.26
				SGST-Inv(9.00%)	INR	1,034.26
(286)	Sac : 995462 - Supply of 100mm PVC floor trap Providing and fixing including labour for fixing in position PVC Floor trap with 75mm dia outlet and a trap seal of 50mm for kitchen and bath wet area & 20 to 25mm for dry area. If two or three floor trap connections are with 'Y' or separately connected with waste lines, then all floor traps shall be of 50mm water seal. Making proper connection, cutting chase / hole in floors /slabs and bringing the same in proper condition and shape after placing the trap in right position complete as required with encasing in CC M-15.	17	NOS	230.10	3,911.70	
				CGST Inv(9.00%)	INR	352.05
				SGST-Inv(9.00%)	INR	352.05
(287)	Sac : 995462 - Inst of 100mm PVC floor trap	17	NOS	70.80	1,203.60	
				CGST Inv(9.00%)	INR	108.32
				SGST-Inv(9.00%)	INR	108.32
(288)	Sac : 995462 - T&C of 100mm PVC floor trap	17	NOS	35.40	601.80	
				CGST Inv(9.00%)	INR	54.16
				SGST-Inv(9.00%)	INR	54.16
(289)	Sac : 995462 - Handover of 100mm PVC floor trap	17	NOS	17.70	300.90	

Corporate Addr.:514, Dalmal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	27.08
				SGST-Inv(9.00%)	INR	27.08
(290)	Sac : 995462 - Supply of 100mm PVC floor trap	382	NOS	325.00	124,150.00	
				CGST Inv(9.00%)	INR	11,173.50
				SGST-Inv(9.00%)	INR	11,173.50
(291)	Sac : 995462 - Inst of 100mm PVC floor trap	382	NOS	100.00	38,200.00	
				CGST Inv(9.00%)	INR	3,438.00
				SGST-Inv(9.00%)	INR	3,438.00
(292)	Sac : 995462 - T&C of 100mm PVC floor trap	382	NOS	50.00	19,100.00	
				CGST Inv(9.00%)	INR	1,719.00
				SGST-Inv(9.00%)	INR	1,719.00
(293)	Sac : 995462 - Handover of 100mm PVC floor trap	382	NOS	25.00	9,550.00	
				CGST Inv(9.00%)	INR	859.50
				SGST-Inv(9.00%)	INR	859.50
(294)	Sac : 995462 - Supply of 100mm PVC floor trap	199	NOS	230.10	45,789.90	
				CGST Inv(9.00%)	INR	4,121.09
				SGST-Inv(9.00%)	INR	4,121.09
(295)	Sac : 995462 - Inst of 100mm PVC floor trap	199	NOS	70.80	14,089.20	
				CGST Inv(9.00%)	INR	1,268.03
				SGST-Inv(9.00%)	INR	1,268.03
(296)	Sac : 995462 - T&C of 100mm PVC floor trap	199	NOS	35.40	7,044.60	
				CGST Inv(9.00%)	INR	634.01
				SGST-Inv(9.00%)	INR	634.01
(297)	Sac : 995462 - Handover of 100mm PVC floor trap	199	NOS	17.70	3,522.30	
				CGST Inv(9.00%)	INR	317.01
				SGST-Inv(9.00%)	INR	317.01
(298)	Sac : 995462 - Supply of 100mm PVC floor trap	199	NOS	174.20	34,665.80	
				CGST Inv(9.00%)	INR	3,119.92
				SGST-Inv(9.00%)	INR	3,119.92
(299)	Sac : 995462 - Inst of 100mm PVC floor trap	199	NOS	53.60	10,666.40	

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	959.98
				SGST-Inv(9.00%)	INR	959.98
(300)	Sac : 995462 - T&C of 100mm PVC floor trap Providing, fixing, jointing, testing and commissioning of UPVC pipe Type-B for Soil, Waste upto 160mm dia. confirming to IS 13592 cut to required lengths including all necessary fittings and specials such as as 45 or 90 deg. bends, Tee's, Y's, access pipe with solvent cement jointing. (For Pipes buried in flooring). Setting the pipes in cement concrete M-15, 100mm all around of pipes as per specifications after testing of pipes. SWR range pasted pipes (Type-B) & fittings (without rubber rings) with solvent joints for all sunken area (concealed) piping for toilets / kitchens (Water testing of pipes to be done after 12 hours, after last solvent cement joint. Where ever possible use Aqua Drain test plugs for testing of lines.) Including civil material for pcc*encasing (concrete quantity considered separately).	199	NOS	26.80	5,333.20	
				CGST Inv(9.00%)	INR	479.99
				SGST-Inv(9.00%)	INR	479.99
(301)	Sac : 995462 - Handover of 100mm PVC floor trap	199	NOS	13.40	2,666.60	
				CGST Inv(9.00%)	INR	239.99
				SGST-Inv(9.00%)	INR	239.99
(302)	Sac : 995462 - Supply of 110mm UPVC Pipe Type B Providing, fixing, jointing, testing and commissioning of UPVC pipe Type-B for Soil, Waste upto 160mm dia. confirming to IS 13592 cut to required lengths including all necessary fittings and specials such as as 45 or 90 deg. bends, Tee's, Y's, access pipe with solvent cement jointing. (For Pipes buried in flooring). Setting the pipes in cement concrete M-15, 100mm all around of pipes as per specifications after testing of pipes. SWR range pasted pipes (Type-B) & fittings (without rubber rings) with solvent joints for all sunken area (concealed) piping for toilets / kitchens (Water testing of pipes to be done after 12 hours, after last solvent cement joint. Where ever possible use Aqua Drain test plugs for testing of lines.) Including civil material for pcc*encasing (concrete quantity considered separately).	90	M	310.70	27,963.00	
				CGST Inv(9.00%)	INR	2,516.67
				SGST-Inv(9.00%)	INR	2,516.67
(303)	Sac : 995462 - Inst of 110mm UPVC Pipe Type B	90	M	95.60	8,604.00	
				CGST Inv(9.00%)	INR	774.36
				SGST-Inv(9.00%)	INR	774.36
(304)	Sac : 995462 - T&C of 110mm UPVC Pipe Type B	90	M	47.80	4,302.00	
				CGST Inv(9.00%)	INR	387.18
				SGST-Inv(9.00%)	INR	387.18
(305)	Sac : 995462 - Handover of 110mm UPVC Pipe Type B	90	M	23.90	2,151.00	
				CGST Inv(9.00%)	INR	193.59
				SGST-Inv(9.00%)	INR	193.59
(306)	Sac : 995462 - Supply of 110mm UPVC Pipe Type B	70	M	310.70	21,749.00	

Corporate Addr.:514, Dalmal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	1,957.41
				SGST-Inv(9.00%)	INR	1,957.41
(307)	Sac : 995462 - Inst of 110mm UPVC Pipe Type B	70	M	95.60		6,692.00
				CGST Inv(9.00%)	INR	602.28
				SGST-Inv(9.00%)	INR	602.28
(308)	Sac : 995462 - T&C of 110mm UPVC Pipe Type B	70	M	47.80		3,346.00
				CGST Inv(9.00%)	INR	301.14
				SGST-Inv(9.00%)	INR	301.14
(309)	Sac : 995462 - Handover of 110mm UPVC Pipe Type B	70	M	23.90		1,673.00
				CGST Inv(9.00%)	INR	150.57
				SGST-Inv(9.00%)	INR	150.57
(310)	Sac : 995462 - Supply of 75mm UPVC Pipe Type B	10	M	219.70		2,197.00
				CGST Inv(9.00%)	INR	197.73
				SGST-Inv(9.00%)	INR	197.73
(311)	Sac : 995462 - Inst of 75mm UPVC Pipe Type B	10	M	67.60		676.00
				CGST Inv(9.00%)	INR	60.84
				SGST-Inv(9.00%)	INR	60.84
(312)	Sac : 995462 - T&C of 75mm UPVC Pipe Type B	10	M	33.80		338.00
				CGST Inv(9.00%)	INR	30.42
				SGST-Inv(9.00%)	INR	30.42
(313)	Sac : 995462 - Handover of 75mm UPVC Pipe Type B	10	M	16.90		169.00
				CGST Inv(9.00%)	INR	15.21
				SGST-Inv(9.00%)	INR	15.21
(314)	Sac : 995462 - Supply of 75mm UPVC Pipe Type B	200	M	219.70		43,940.00
				CGST Inv(9.00%)	INR	3,954.60
				SGST-Inv(9.00%)	INR	3,954.60
(315)	Sac : 995462 - Inst of 75mm UPVC Pipe Type B	200	M	67.60		13,520.00
				CGST Inv(9.00%)	INR	1,216.80
				SGST-Inv(9.00%)	INR	1,216.80
(316)	Sac : 995462 - T&C of 75mm UPVC Pipe Type B	200	M	33.80		6,760.00

Corporate Addr.:514, Dalmal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	608.40
				SGST-Inv(9.00%)	INR	608.40
(317)	Sac : 995462 - Handover of 75mm UPVC Pipe Type B Providing, fixing, jointing, testing and commissioning of UPVC pipe Agri. range 6 kgf pipes and fittings for 40, 50 & 63mm dia. cut to required lengths including all necessary fittings and specials such as as 45 or 90 deg. bends, Tee's, Y's, access pipe with solvent cement jointing. Vertical pipes (above sunk level) in necessary wall chases and finishing of same with geru mixed cement mortar. Including civil material for pcc+encasing (concrete quantity considered separately). Setting the pipes in cement concrete M-15, 100mm all around of pipes as per specifications after testing of pipes. (Water testing of pipes to be done after 12 hours, after last solvent cement joint. Where ever possible use Aqua Drain test plugs for testing of lines.) . For Pipes Buried in Toilets / kit. from Wash Basin, Sink, etc to Floor trap / Main Drain (50mmx25mm reducer socket and 40mmx25mm reducer socket shall be fixed for washing machine / dish washer outlet).	200	M	16.90	3,380.00	
				CGST Inv(9.00%)	INR	304.20
				SGST-Inv(9.00%)	INR	304.20
(318)	Sac : 995462 - Supply of 40mm UPVC Pipe Agri 6kgf Providing, fixing, jointing, testing and commissioning of UPVC pipe Agri. range 6 kgf pipes and fittings for 40, 50 & 63mm dia. cut to required lengths including all necessary fittings and specials such as as 45 or 90 deg. bends, Tee's, Y's, access pipe with solvent cement jointing. Vertical pipes (above sunk level) in necessary wall chases and finishing of same with geru mixed cement mortar. Including civil material for pcc+encasing (concrete quantity considered separately). Setting the pipes in cement concrete M-15, 100mm all around of pipes as per specifications after testing of pipes. (Water testing of pipes to be done after 12 hours, after last solvent cement joint. Where ever possible use Aqua Drain test plugs for testing of lines.) . For Pipes Buried in Toilets / kit. from Wash Basin, Sink, etc to Floor trap / Main Drain (50mmx25mm reducer socket and 40mmx25mm reducer socket shall be fixed for washing machine / dish washer outlet).	40	M	57.85	2,314.00	
				CGST Inv(9.00%)	INR	208.26
				SGST-Inv(9.00%)	INR	208.26
(319)	Sac : 995462 - Inst of 40mm UPVC Pipe Agri 6kgf	40	M	17.80	712.00	
				CGST Inv(9.00%)	INR	64.08
				SGST-Inv(9.00%)	INR	64.08
(320)	Sac : 995462 - T&C of 40mm UPVC Pipe Agri 6kgf	40	M	8.90	356.00	
				CGST Inv(9.00%)	INR	32.04
				SGST-Inv(9.00%)	INR	32.04
(321)	Sac : 995462 - Handover of 40mm UPVC Pipe Agri 6kgf	40	M	4.45	178.00	
				CGST Inv(9.00%)	INR	16.02
				SGST-Inv(9.00%)	INR	16.02
(322)	Sac : 995462 - Supply of 40mm UPVC Pipe Agri 6kgf	400	M	57.85	23,140.00	
				CGST Inv(9.00%)	INR	2,082.60



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				SGST-Inv(9.00%)	INR	2,082.60
(323)	Sac : 995462 - Inst of 40mm UPVC Pipe Agri 6kgf	400	M	17.80	7,120.00	
				CGST Inv(9.00%)	INR	640.80
				SGST-Inv(9.00%)	INR	640.80
(324)	Sac : 995462 - T&C of 40mm UPVC Pipe Agri 6kgf	400	M	8.90	3,560.00	
				CGST Inv(9.00%)	INR	320.40
				SGST-Inv(9.00%)	INR	320.40
(325)	Sac : 995462 - Handover of 40mm UPVC Pipe Agri 6kgf	400	M	4.45	1,780.00	
				CGST Inv(9.00%)	INR	160.20
				SGST-Inv(9.00%)	INR	160.20
(326)	Sac : 995462 - Supply of 50mm UPVC Pipe Agri 6kgf	10	M	81.25	812.50	
				CGST Inv(9.00%)	INR	73.13
				SGST-Inv(9.00%)	INR	73.13
(327)	Sac : 995462 - Inst of 50mm UPVC Pipe Agri 6kgf	10	M	25.00	250.00	
				CGST Inv(9.00%)	INR	22.50
				SGST-Inv(9.00%)	INR	22.50
(328)	Sac : 995462 - T&C of 50mm UPVC Pipe Agri 6kgf	10	M	12.50	125.00	
				CGST Inv(9.00%)	INR	11.25
				SGST-Inv(9.00%)	INR	11.25
(329)	Sac : 995462 - Handover of 50mm UPVC Pipe Agri 6kgf	10	M	6.25	62.50	
				CGST Inv(9.00%)	INR	5.63
				SGST-Inv(9.00%)	INR	5.63

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value
(330)	Sac : 995462 - Supply of 40mm UPVC pasted pipe Type B Providing and fixing including labour for fixing UPVC pasted pipes (Type-B) & fittings (without rubber rings) with solvent joints of 75 & 110mm dia. and Agri. range 6 kgf pipes and fittings for 40, 50 & 63mm dia. for all suspended horizontal piping for toilets / kitchens including all necessary fittings and specials such as as 45 or 90 deg. bends, Tee's, Y's, access pipe etc. Pipe portion going in concrete area shall be applied with solvent and fine sand. (Water testing of pipes to be done after 12 hours, after last solvent cement joint. Where ever possible use Aqua Drain test plugs for testing of lines.) Supports shall be Split clamp with rubber lining for entire suspended pipings as per specs. Split clamp rod & Anchor bolt dia. # 8mm for 40mm & 50mm pipes and 10mm for 63mm, 75mm and 110mm pipes. Additional supports to be provided near fittings if required as per site condition & instructions of engineer in-charge. Horizontal supports spacing (Center to Center) shall be as follows - 40mm = 400mm / 50mm= 500mm / 75mm= 750mm / 110mm = 1000mm / 160mm & above = 1500mm. For suspended pipes in Toilets / kitchens from Wash Basin, Sink, Washing Machine, Dish Washer etc to 'P' Trap. Supports required at bottom of 'P' Trap & Floor Trap. Vertical pipes (above slab level) in necessary wall chases and finishing of same with geru mixed cement mortar. Horizontal SWR drains for 50 / 65mm sunk toilets and Kitchens (suspended piping) (50mm x 25mm reducer socket and 40mm x 25mm reducer socket shall be fixed for washing machine / dish washer outlet).	650	M	141.05	91,682.50
(331)	Sac : 995462 - Inst of 40mm UPVC pasted pipe Type B CGST Inv(9.00%) INR 8,251.43 SGST-Inv(9.00%) INR 8,251.43	650	M	43.40	28,210.00
(332)	Sac : 995462 - T&C of 40mm UPVC pasted pipe Type B CGST Inv(9.00%) INR 2,538.90 SGST-Inv(9.00%) INR 2,538.90	650	M	21.70	14,105.00
(333)	Sac : 995462 - Handover of 40mm UPVC pasted pipe Type B CGST Inv(9.00%) INR 634.73 SGST-Inv(9.00%) INR 634.73	650	M	10.85	7,052.50



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
(334)	Sac : 995462 - Supply of 75mm UPVC pasted pipe Type B	185	M	323.70		59,884.50
				CGST Inv(9.00%)	INR	5,389.61
				SGST-Inv(9.00%)	INR	5,389.61
(335)	Sac : 995462 - Inst of 75mm UPVC pasted pipe Type B	185	M	99.60		18,426.00
				CGST Inv(9.00%)	INR	1,658.34
				SGST-Inv(9.00%)	INR	1,658.34
(336)	Sac : 995462 - T&C of 75mm UPVC pasted pipe Type B	185	M	49.80		9,213.00
				CGST Inv(9.00%)	INR	829.17
				SGST-Inv(9.00%)	INR	829.17
(337)	Sac : 995462 - Handover of 75mm UPVC pasted pipe Type B	185	M	24.90		4,606.50
				CGST Inv(9.00%)	INR	414.59
				SGST-Inv(9.00%)	INR	414.59
(338)	Sac : 995462 - Supply of 110mm UPVC pasted pipe Type B	660	M	446.55		294,723.00
				CGST Inv(9.00%)	INR	26,525.07
				SGST-Inv(9.00%)	INR	26,525.07
(339)	Sac : 995462 - Inst of 110mm UPVC pasted pipe Type B	660	M	137.40		90,684.00
				CGST Inv(9.00%)	INR	8,161.56
				SGST-Inv(9.00%)	INR	8,161.56
(340)	Sac : 995462 - T&C of 110mm UPVC pasted pipe Type B	660	M	68.70		45,342.00
				CGST Inv(9.00%)	INR	4,080.78
				SGST-Inv(9.00%)	INR	4,080.78
(341)	Sac : 995462 - Handover of 110mm UPVC pasted pipe Type	660	M	34.35		22,671.00
				CGST Inv(9.00%)	INR	2,040.39
				SGST-Inv(9.00%)	INR	2,040.39

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value
(342)	Sac : 995462 - Supply of 25mm UPVC agricultural pipe Providing, fixing, Testing and Commissioning uPVC agricultural pipe with necessary fittings, GI brackets, clamps, split clamp with rubber etc. complete. Concealed / false ceiling area pipes if any, with elastomeric rubber insulation (clamps shall be fixed after insulation) and exposed area pipes without insulation & supports at 1 mtr. c/c. (For A.C. Drain connection in shaft, 'U' trap to be done with using fittings before connecting to vertical pipe) Quantity to be check & order as per site condition.	170	M	97.50	16,575.00
				CGST Inv(9.00%)	INR 1,491.75
				SGST-Inv(9.00%)	INR 1,491.75
(343)	Sac : 995462 - Inst of 25mm UPVC agricultural pipe	170	M	30.00	5,100.00
				CGST Inv(9.00%)	INR 459.00
				SGST-Inv(9.00%)	INR 459.00
(344)	Sac : 995462 - T&C of 25mm UPVC agricultural pipe	170	M	15.00	2,550.00
				CGST Inv(9.00%)	INR 229.50
				SGST-Inv(9.00%)	INR 229.50
(345)	Sac : 995462 - Handover of 25mm UPVC agricultural pipe	170	M	7.50	1,275.00
				CGST Inv(9.00%)	INR 114.75
				SGST-Inv(9.00%)	INR 114.75
(346)	Sac : 995462 - Supply of 100mm CI spigot and socket pip Providing, fixing, jointing, testing and commissioning of heavy quality approved make CI spigot and socket pipes for soil, waste and vent, conforming to IS 3989 including all fittings like offsets, 45 deg. bends, single or double junctions of different degrees, with access doors, etc. including providing & fixing with caulking spun yarn and DRIP seal jointing with testing of pipes and making the joints leak proof, including fixing them vertically against walls on M.S. Hot dip Galvanised brackets & G.I. 'U' clamps or hangers including all scaffolding, testing after laying the pipes as specified etc. Complete. Vertical SWR drains in shafts for toilets / kit. (ground) with C.I. Cleaning pc. at bottom. (where applicable).	8	M	991.25	7,930.00
				CGST Inv(9.00%)	INR 713.70
				SGST-Inv(9.00%)	INR 713.70

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
(347)	Sac : 995462 - Inst of 100mm CI spigot and socket pipes	8	M	305.00	2,440.00	
				CGST Inv(9.00%)	INR	219.60
				SGST-Inv(9.00%)	INR	219.60
(348)	Sac : 995462 - T&C of 100mm CI spigot and socket pipes	8	M	152.50	1,220.00	
				CGST Inv(9.00%)	INR	109.80
				SGST-Inv(9.00%)	INR	109.80
(349)	Sac : 995462 - Handover of 100mm CI spigot and socket p	8	M	76.25	610.00	
				CGST Inv(9.00%)	INR	54.90
				SGST-Inv(9.00%)	INR	54.90
(350)	Sac : 995462 - Supply of 100mm PVC WC Connector Providing and fixing P.V.C. WC connector with rubber lip ring to suit WC outlet and proper connection complete as required .	1	NOS	162.50	162.50	
				CGST Inv(9.00%)	INR	14.63
				SGST-Inv(9.00%)	INR	14.63
(351)	Sac : 995462 - Inst of 100mm PVC WC Connector	1	NOS	50.00	50.00	
				CGST Inv(9.00%)	INR	4.50
				SGST-Inv(9.00%)	INR	4.50
(352)	Sac : 995462 - T&C of 100mm PVC WC Connector	1	NOS	25.00	25.00	
				CGST Inv(9.00%)	INR	2.25
				SGST-Inv(9.00%)	INR	2.25
(353)	Sac : 995462 - Handover of 100mm PVC WC Connector	1	NOS	12.50	12.50	
				CGST Inv(9.00%)	INR	1.13
				SGST-Inv(9.00%)	INR	1.13
(354)	Sac : 995462 - Supply of PVC 'P' (110mm x 75mm) Trap Providing and fixing including labour for fixing in position PVC 'P' (110mm x 75mm) Trap with necessary support at bottom. Connection with pvc puddle sleeve provided with solvent joint etc. complete. For toilet shaft drains	1	NOS	552.50	552.50	

Corporate Addr.:514, Dalmal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	49.73
				SGST-Inv(9.00%)	INR	49.73
(355)	Sac : 995462 - Inst of PVC 'P' (110mm x 75mm) Trap	1	NOS	170.00	170.00	
				CGST Inv(9.00%)	INR	15.30
				SGST-Inv(9.00%)	INR	15.30
(356)	Sac : 995462 - T&C of PVC 'P' (110mm x 75mm) Trap	1	NOS	85.00	85.00	
				CGST Inv(9.00%)	INR	7.65
				SGST-Inv(9.00%)	INR	7.65
(357)	Sac : 995462 - Handover of PVC 'P' (110mm x 75mm) Trap	1	NOS	42.50	42.50	
				CGST Inv(9.00%)	INR	3.83
				SGST-Inv(9.00%)	INR	3.83
(358)	Sac : 995462 - Supply of uPVC Puddle Flange 110X600mm Providing, fixing, Testing and Commissioning of uPVC Puddle Flanges (Type-B pipe only) including fixing with BCP screws (35 x 8), 4 nos. per flange. Center of flange shall be as per w.c. outlet & 'P' Trap outlet dimensions and same shall be in plumb before fixing screws.	764	NOS	539.50	412,178.00	
				CGST Inv(9.00%)	INR	37,096.02
				SGST-Inv(9.00%)	INR	37,096.02
(359)	Sac : 995462 - Inst of uPVC Puddle Flange 110X600mm	764	NOS	166.00	126,824.00	
				CGST Inv(9.00%)	INR	11,414.16
				SGST-Inv(9.00%)	INR	11,414.16
(360)	Sac : 995462 - T&C of uPVC Puddle Flange 110X600mm	764	NOS	83.00	63,412.00	
				CGST Inv(9.00%)	INR	5,707.08
				SGST-Inv(9.00%)	INR	5,707.08
(361)	Sac : 995462 - Handover of uPVC Puddle Flange 110X600mm	764	NOS	41.50	31,706.00	
				CGST Inv(9.00%)	INR	2,853.54
				SGST-Inv(9.00%)	INR	2,853.54



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
(362)	Sac : 995462 - Supply of uPVC Puddle Flange 40X600mm	382	NOS	211.25	80,697.50	
				CGST Inv(9.00%)	INR	7,262.78
				SGST-Inv(9.00%)	INR	7,262.78
(363)	Sac : 995462 - Inst of uPVC Puddle Flange 40X600mm	382	NOS	65.00	24,830.00	
				CGST Inv(9.00%)	INR	2,234.70
				SGST-Inv(9.00%)	INR	2,234.70
(364)	Sac : 995462 - T&C of uPVC Puddle Flange 40X600mm	382	NOS	32.50	12,415.00	
				CGST Inv(9.00%)	INR	1,117.35
				SGST-Inv(9.00%)	INR	1,117.35
(365)	Sac : 995462 - Handover of uPVC Puddle Flange 40X600mm	382	NOS	16.25	6,207.50	
				CGST Inv(9.00%)	INR	558.68
				SGST-Inv(9.00%)	INR	558.68
(366)	Sac : 995462 - Supply of 150mm C.I. Grating Providing, Fixing, Testing & Commissioning of C.I. rain water Grating.	4	NOS	211.25	845.00	
				CGST Inv(9.00%)	INR	76.05
				SGST-Inv(9.00%)	INR	76.05
(367)	Sac : 995462 - Inst of 150mm C.I. Grating	4	NOS	65.00	260.00	
				CGST Inv(9.00%)	INR	23.40
				SGST-Inv(9.00%)	INR	23.40
(368)	Sac : 995462 - T&C of 150mm C.I. Grating	4	NOS	32.50	130.00	
				CGST Inv(9.00%)	INR	11.70
				SGST-Inv(9.00%)	INR	11.70
(369)	Sac : 995462 - Handover of 150mm C.I. Grating	4	NOS	16.25	65.00	
				CGST Inv(9.00%)	INR	5.85
				SGST-Inv(9.00%)	INR	5.85
(370)	Sac : 995462 - Supply of 200X200 C.I. Grating	8	NOS	373.75	2,990.00	
				CGST Inv(9.00%)	INR	269.10
				SGST-Inv(9.00%)	INR	269.10

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
(371)	Sac : 995462 - Inst of 200X200 C.I. Grating	8	NOS	115.00	920.00	
				CGST Inv(9.00%)	INR	82.80
				SGST-Inv(9.00%)	INR	82.80
(372)	Sac : 995462 - T&C of 200X200 C.I. Grating	8	NOS	57.50	460.00	
				CGST Inv(9.00%)	INR	41.40
				SGST-Inv(9.00%)	INR	41.40
(373)	Sac : 995462 - Handover of 200X200 C.I. Grating	8	NOS	28.75	230.00	
				CGST Inv(9.00%)	INR	20.70
				SGST-Inv(9.00%)	INR	20.70
(374)	Sac : 995462 - Supply of 150X150 C.I. Grating	8	NOS	318.50	2,548.00	
				CGST Inv(9.00%)	INR	229.32
				SGST-Inv(9.00%)	INR	229.32
(375)	Sac : 995462 - Inst of 150X150 C.I. Grating	8	NOS	98.00	784.00	
				CGST Inv(9.00%)	INR	70.56
				SGST-Inv(9.00%)	INR	70.56
(376)	Sac : 995462 - T&C of 150X150 C.I. Grating	8	NOS	49.00	392.00	
				CGST Inv(9.00%)	INR	35.28
				SGST-Inv(9.00%)	INR	35.28
(377)	Sac : 995462 - Handover of 150X150 C.I. Grating	8	NOS	24.50	196.00	
				CGST Inv(9.00%)	INR	17.64
				SGST-Inv(9.00%)	INR	17.64
(378)	Sac : 995462 - Excavation not exceeding 1.5m EXTERNAL SEWAGE / RAIN WATER DRAINAGE	250	M3	290.00	72,500.00	
	Excavation in trenches for pipelines including trimming bottom and sides, cutting for sockets, ramming of bottom and disposal of surplus earth etc. Depth of Excavation not exceeding 1.5m (Excavation in all classes of soil).			CGST Inv(9.00%)	INR	6,525.00
				SGST-Inv(9.00%)	INR	6,525.00
(379)	Sac : 995462 - Excavation Extra over 1.1 above for dept Extra over 1.1 above for depths exceeding 1.5m but not greater than 2.5m (Excavation in all classes of soil).	110	M3	345.00	37,950.00	



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	3,415.50
				SGST-Inv(9.00%)	INR	3,415.50
(380)	Sac : 995462 - P&L cement concrete M-15 for PCC / Encas Providing and laying cement concrete M-15 as per specifications for PCC / Encasing / Foundation etc, (including 250mm sunk toilet / kitchen / balcony pipe encasing)	80	M3	5,500.00	440,000.00	
				CGST Inv(9.00%)	INR	39,600.00
				SGST-Inv(9.00%)	INR	39,600.00
(381)	Sac : 995462 - Backfilling of trenches with murum / soil	200	M3	73.00	14,600.00	
				CGST Inv(9.00%)	INR	1,314.00
				SGST-Inv(9.00%)	INR	1,314.00
(382)	Sac : 995462 - Supply of 160mm UPVC pipe Providing, fixing, jointing and testing in position the following UPVC pipes confirming to IS: 4985 of 6 Kg / Sq.cm for drainage system cut to required length. Pipe to be laid below ground level in trenches upto required depth, dewatering, jointing of pipes with solvent cement, water testing of joints after 1 hour and setting the pipes in cement concrete M-15 as per specifications 150mm thk. all around, refilling of trenches, and making good the same complete as required. Scope of work includes piping and manholes upto existing manhole or municipal manhole on road and connection with breaking the wall of municipal / road manhole and making good the same with Cement mortar 1:3, finished with a floating coat of neat cement and making the same good etc. complete. For RWP System from Plumbing duct to RW chamber, Drain chamber Branch pipes. Including civil material for pcc+encasing (concrete quantity considered separately)	25	M	536.25	13,406.25	
				CGST Inv(9.00%)	INR	1,206.56
				SGST-Inv(9.00%)	INR	1,206.56
(383)	Sac : 995462 - Inst of 160mm UPVC pipe	25	M	165.00	4,125.00	
				CGST Inv(9.00%)	INR	371.25
				SGST-Inv(9.00%)	INR	371.25
(384)	Sac : 995462 - T&C of 160mm UPVC pipe	25	M	82.50	2,062.50	



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	185.63
				SGST-Inv(9.00%)	INR	185.63
(385)	Sac : 995462 - Handover of 160mm UPVC pipe	25	M	41.25		1,031.25
				CGST Inv(9.00%)	INR	92.81
				SGST-Inv(9.00%)	INR	92.81
(386)	Sac : 995462 - Supply of 110mm UPVC pipe	60	M	258.70		15,522.00
				CGST Inv(9.00%)	INR	1,396.98
				SGST-Inv(9.00%)	INR	1,396.98
(387)	Sac : 995462 - Inst of 110mm UPVC pipe	60	M	79.60		4,776.00
				CGST Inv(9.00%)	INR	429.84
				SGST-Inv(9.00%)	INR	429.84
(388)	Sac : 995462 - T&C of 110mm UPVC pipe	60	M	39.80		2,388.00
				CGST Inv(9.00%)	INR	214.92
				SGST-Inv(9.00%)	INR	214.92
(389)	Sac : 995462 - Handover of 110mm UPVC pipe	60	M	19.90		1,194.00
				CGST Inv(9.00%)	INR	107.46
				SGST-Inv(9.00%)	INR	107.46
(390)	Sac : 995462 - Supply of 75mm UPVC pipe	20	M	123.50		2,470.00
				CGST Inv(9.00%)	INR	222.30
				SGST-Inv(9.00%)	INR	222.30
(391)	Sac : 995462 - Inst of 75mm UPVC pipe	20	M	38.00		760.00
				CGST Inv(9.00%)	INR	68.40
				SGST-Inv(9.00%)	INR	68.40
(392)	Sac : 995462 - T&C of 75mm UPVC pipe	20	M	19.00		380.00
				CGST Inv(9.00%)	INR	34.20
				SGST-Inv(9.00%)	INR	34.20
(393)	Sac : 995462 - Handover of 75mm UPVC pipe	20	M	9.50		190.00
				CGST Inv(9.00%)	INR	17.10
				SGST-Inv(9.00%)	INR	17.10

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value
(394)	Sac : 995462 - Supply of 150mm HDPE pipe(SN8) Providing, fixing, jointing and testing in position the following Double wall corrugated H.D.P.E. pipes, for non pressure storm water and sewerage applications. (As per ISO 21138 # 3) for drainage system cut to required length. Pipe to be laid below ground level in trenches upto required depth, dewatering, jointing of pipes with solvent cement, water testing of joints after 1 hour and setting the pipes in cement concrete M-15 as per specifications 150mm thk. all around, refilling of trenches, and making good the same complete as required. Scope of work includes piping and manholes upto existing manhole or municipal manhole on road and connection with breaking the wall of municipal / road manhole and making good the same with Cement mortar 1:3, finished with a floating coat of neat cement and making the same good etc. complete. For RWP System from building to SWD, RWH Piping, Building Drainage etc. - Main and Branch pipes. DWC SN4 pipes shall be used up to 1.5mtr. deep drain lines and SN8 pipes shall be used if depth is more than 1.5 mtr. Including civil material for pcc+encasing (concrete quantity considered separately).	80	M	375.70	30,056.00
				CGST Inv(9.00%)	INR 2,705.04
				SGST-Inv(9.00%)	INR 2,705.04
(395)	Sac : 995462 - Inst of 150mm HDPE pipe(SN8)	80	M	115.60	9,248.00
				CGST Inv(9.00%)	INR 832.32
				SGST-Inv(9.00%)	INR 832.32
(396)	Sac : 995462 - T&C of 150mm HDPE pipe(SN8)	80	M	57.80	4,624.00
				CGST Inv(9.00%)	INR 416.16
				SGST-Inv(9.00%)	INR 416.16
(397)	Sac : 995462 - Handover of 150mm HDPE pipe(SN8)	80	M	28.90	2,312.00
				CGST Inv(9.00%)	INR 208.08
				SGST-Inv(9.00%)	INR 208.08
(398)	Sac : 995462 - Supply of 200mm HDPE pipe(SN8)	80	M	589.55	47,164.00
				CGST Inv(9.00%)	INR 4,244.76
				SGST-Inv(9.00%)	INR 4,244.76
(399)	Sac : 995462 - Inst of 200mm HDPE pipe(SN8)	80	M	181.40	14,512.00



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	1,306.08
				SGST-Inv(9.00%)	INR	1,306.08
(400)	Sac : 995462 - T&C of 200mm HDPE pipe(SN8)	80	M	90.70		7,256.00
				CGST Inv(9.00%)	INR	653.04
				SGST-Inv(9.00%)	INR	653.04
(401)	Sac : 995462 - Handover of 200mm HDPE pipe(SN8)	80	M	45.35		3,628.00
				CGST Inv(9.00%)	INR	326.52
				SGST-Inv(9.00%)	INR	326.52
(402)	Sac : 995462 - Supply of 250mm HDPE pipe(SN8)	20	M	884.00		17,680.00
				CGST Inv(9.00%)	INR	1,591.20
				SGST-Inv(9.00%)	INR	1,591.20
(403)	Sac : 995462 - Inst of 250mm HDPE pipe(SN8)	20	M	272.00		5,440.00
				CGST Inv(9.00%)	INR	489.60
				SGST-Inv(9.00%)	INR	489.60
(404)	Sac : 995462 - T&C of 250mm HDPE pipe(SN8)	20	M	136.00		2,720.00
				CGST Inv(9.00%)	INR	244.80
				SGST-Inv(9.00%)	INR	244.80
(405)	Sac : 995462 - Handover of 250mm HDPE pipe(SN8)	20	M	68.00		1,360.00
				CGST Inv(9.00%)	INR	122.40
				SGST-Inv(9.00%)	INR	122.40
(406)	Sac : 995462 - Supply of 300mm HDPE pipe(SN8)	25	M	1,300.00		32,500.00
				CGST Inv(9.00%)	INR	2,925.00
				SGST-Inv(9.00%)	INR	2,925.00
(407)	Sac : 995462 - Inst of 300mm HDPE pipe(SN8)	25	M	400.00		10,000.00
				CGST Inv(9.00%)	INR	900.00
				SGST-Inv(9.00%)	INR	900.00
(408)	Sac : 995462 - T&C of 300mm HDPE pipe(SN8)	25	M	200.00		5,000.00
				CGST Inv(9.00%)	INR	450.00
				SGST-Inv(9.00%)	INR	450.00
(409)	Sac : 995462 - Handover of 300mm HDPE pipe(SN8)	25	M	100.00		2,500.00

Corporate Addr.:514, Dalmal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value
				CGST Inv(9.00%)	INR 225.00
				SGST-Inv(9.00%)	INR 225.00
(410)	Sac : 995462 - P&F pvc Bottle gully trap Providing and fixing round mouthed pvc Bottle gully trap with 300mm x 300mm chamber with CI cover at top including embedding the trap in cement concrete M-15 construction of brick masonry chamber internal clear size 300 x 300 mm in brick masonry 250mm thick in cement sand mortar 1:4 over M-15 cement concrete bed 150mm thick, plastering inside outside and all exposed surfaces with 1:3 cement sand plaster 15mm thick. Including providing and fixing of CI frame & cover size 300 x 300mm weighing together not less than 7.8Kgms painting all CI items with 3 coats of approved bituminastic paint etc. complete. For all waste lines including AC / Balcony / Shaft drain lines etc.	21	NOS	4,650.00	97,650.00
				CGST Inv(9.00%)	INR 8,788.50
				SGST-Inv(9.00%)	INR 8,788.50
(411)	Sac : 995462 - P&C inspection chamber with 80 kg DI Cov Providing & Constructing block masonry inspection chamber of below sizes and depth upto 1375mm including the following: a) 200 thick block masonry walls in CM 1:4 b) C.C. foundation bed in M-15, 150 mm thick size 1600 x 1150 c) Cement plaster inside and outside in CM 1:3 (with cement ghotal from inside) d) CC M-15 in haunches and channels finished smooth in CM 1:2 e) C C M-15 cap on top 200 thick f) Providing & fixing of Ductile / Cast iron cover & frame g) 75 wide fillet (wata) all round block / brick masonry and c.c. bed in CM 1:3 h) All excavation in any type of soil removal and disposing off surplus earth after backfilling as directed including dewatering. All civil materials in contractors scope. 900mm x 450mm	9	NOS	21,500.00	193,500.00
				CGST Inv(9.00%)	INR 17,415.00
				SGST-Inv(9.00%)	INR 17,415.00
(412)	Sac : 995462 - P&C inspection chamber with 104 kg DI Co 900mm x 600mm	2	NOS	27,500.00	55,000.00

Corporate Addr.:514, Dalal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	4,950.00
				SGST-Inv(9.00%)	INR	4,950.00
(413)	Sac : 995462 - P&C inspection chamber with 62 kg DI Cov 600mm x 600mm	8	NOS	17,500.00		140,000.00
				CGST Inv(9.00%)	INR	12,600.00
				SGST-Inv(9.00%)	INR	12,600.00
(414)	Sac : 995462 - P&C conical manholes with 60 kg DI Cover Providing & Constructing brick masonry conical manholes including the following: a) Bed PCC for chamber to be M-15 concrete 200 mm thick, with 6" projection. b) Chamber to be constructed using bricks 225mm thick wall. c) Providing & fixing of Ductile / Cast iron cover & frame d) Plastic steps to be provided. (Copolymer Polypropylene, Steel reinforced manhole step, is injection molded around a 12mm dia. IS-1786 grade Fe-415 steel reinforcing bar.) e) Size of chamber - 1200 mm (for depths > 1375mm and < 2285mm), or 1500 mm (for depth > 2285mm) at bottom, and 0.53 m. at top plaster 1:1 (out) and 1:1 (inside) block masonry 1:3. f) Haunching & benching M-15. g) Depth beyond 2285mm should be in double block 200mm cylindrical. h) C C M-15 cap on top 300 thick i) Cement plaster inside and outside in CM 1:3 (with cement ghotal on both sides) All civil materials in contractors scope. Depth upto 2285mm (1200mm dia. Clear at bottom)	8	NOS	38,900.00		311,200.00
				CGST Inv(9.00%)	INR	28,008.00
				SGST-Inv(9.00%)	INR	28,008.00
(415)	Sac : 995462 - P&C Inspection chamber Left hand 45 deg. Left hand 45 deg. and 90 deg. Junction (315mm x 110mm x 110mm x 110mm) including below items. a) 315mm dia. x 154mm ht. Riser with rubber seal (2 or 3 nos. as per depth) b) 315mm x 315mm Frame & Cover (Heavy duty)	2	NOS	7,500.00		15,000.00
				CGST Inv(9.00%)	INR	1,350.00



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				SGST-Inv(9.00%)	INR	1,350.00
(416)	Sac : 995462 - P&C Inspection chamber Right hand 45 deg Right hand 45 deg. and 90 deg. Junction (315mm x 110mm x 110mm x 110mm) including below items. a) 315mm dia. x 154mm ht. Riser with rubber seal (2 or 3 nos. as per depth) b) 315mm x 315mm Frame & Cover (Heavy duty)	3	NOS	7,500.00		22,500.00
				CGST Inv(9.00%)	INR	2,025.00
				SGST-Inv(9.00%)	INR	2,025.00
(417)	Sac : 995462 - Supply of 80mm CI Centri pipe Providing, Fixing, Testing, & commissioning of Hubless centrifugally cast iron pipes and fittings (Epoxy coated inside & outside) as per ISO-6594 / IS-15905 Standard and jointing with ASTM C1277 marked stainless steel shielded coupling with a double stainless steel bolt & Screw Housing Incorporating a elastometric rubber gasket, system having noise level certification of not more than 25db(A) at 2L/S & inclusive of all necessary specials like bends, tees, offsets, junctions, cowl end plug, inspection pipe, etc. laid under floor/fixed on walls and in pipe shafts. The rate shall be including angle supports, hanger, nuts bolts, anchor fasteners, fixing clamps/ channels with U-bolts, (spacing and details mentioned below) etc. complete. Cutting, chases/holes in floors / walls / slab. (For Soil & Waste Water Pipes upto 300mm Dia. Exposed in Basements) Scope includes, connections of CI pipes with G.I. Puddle flanges provided in retaining wall, including P & F of necessary fittings like thimble pc., tail pc., G.I. flanges, rubber packing, G.I. / S.S. nut-bolt-washer, dripseal joints etc. complete with all respect. Soil line branches shall be connected to main line with using two no. 45 deg. bends. Direct connections with 90 deg. bends are not allowed. (i.e. For all Vertical Soil line connections with Suspended drain lines) Horizontal support spacing for 80mm = 1.0mtr / 100mm = 1.2mtr / 150mm = 1.4mtr / 200mm and higher dia. 1.5mtr. center to center for straight lines. Hanger rod dia. for support clamps # 80 & 100mm = 12mm / 150 & 200mm = 16mm / 300mm = 19mm. (For Suspended drain lines - main & branch at stilt & pump room ceiling piping) Fix Fabricated G.I. Bracket with G.I. 'U' clamps near plumbing shaft (i.e. immediate diversion from vertical line to horizontal line), near bends of main header, near branch tapping with header. (Use 50x50x5 Angle for brackets) and every 5 mtr. Interval for horizontal piping.	3	M	1,105.00		3,315.00



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	298.35
				SGST-Inv(9.00%)	INR	298.35
(418)	Sac : 995462 - Inst of 80mm CI Centri pipe	3	M	340.00		1,020.00
				CGST Inv(9.00%)	INR	91.80
				SGST-Inv(9.00%)	INR	91.80
(419)	Sac : 995462 - T&C of 80mm CI Centri pipe	3	M	170.00		510.00
				CGST Inv(9.00%)	INR	45.90
				SGST-Inv(9.00%)	INR	45.90
(420)	Sac : 995462 - Handover of 80mm CI Centri pipe	3	M	85.00		255.00
				CGST Inv(9.00%)	INR	22.95
				SGST-Inv(9.00%)	INR	22.95
(421)	Sac : 995462 - Supply of 100mm CI Centri pipe	60	M	1,153.75		69,225.00
				CGST Inv(9.00%)	INR	6,230.25
				SGST-Inv(9.00%)	INR	6,230.25
(422)	Sac : 995462 - Inst of 100mm CI Centri pipe	60	M	355.00		21,300.00
				CGST Inv(9.00%)	INR	1,917.00
				SGST-Inv(9.00%)	INR	1,917.00
(423)	Sac : 995462 - T&C of 100mm CI Centri pipe	60	M	177.50		10,650.00
				CGST Inv(9.00%)	INR	958.50
				SGST-Inv(9.00%)	INR	958.50
(424)	Sac : 995462 - Handover of 100mm CI Centri pipe	60	M	88.75		5,325.00
				CGST Inv(9.00%)	INR	479.25
				SGST-Inv(9.00%)	INR	479.25
(425)	Sac : 995462 - Supply of 150mm CI Centri pipe	90	M	2,632.50		236,925.00
				CGST Inv(9.00%)	INR	21,323.25
				SGST-Inv(9.00%)	INR	21,323.25
(426)	Sac : 995462 - Inst of 150mm CI Centri pipe	90	M	810.00		72,900.00
				CGST Inv(9.00%)	INR	6,561.00
				SGST-Inv(9.00%)	INR	6,561.00
(427)	Sac : 995462 - T&C of 150mm CI Centri pipe	90	M	405.00		36,450.00

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	3,280.50
				SGST-Inv(9.00%)	INR	3,280.50
(428)	Sac : 995462 - Handover of 150mm CI Centri pipe Providing, fixing, Testing and Commissioning of CI spun 'P' traps for waste line connections with GI brackets and DRIP seal jointing with testing of joints for leak proof. Waste line branches shall be connected to main line with using single 'Y' & 45 deg. bends. Direct connections with 90 deg. bends are not allowed for waste lines. Vertical Waste line connections with Suspended drain lines. (for AC drain)	90	M	202.50	18,225.00	
				CGST Inv(9.00%)	INR	1,640.25
				SGST-Inv(9.00%)	INR	1,640.25
(429)	Sac : 995462 - Supply of 80mm CI spun P trap Providing, fixing, Testing and Commissioning of CI spun 'P' traps for waste line connections with GI brackets and DRIP seal jointing with testing of joints for leak proof. Waste line branches shall be connected to main line with using single 'Y' & 45 deg. bends. Direct connections with 90 deg. bends are not allowed for waste lines. Vertical Waste line connections with Suspended drain lines. (for AC drain)	2	NOS	2,925.00	5,850.00	
				CGST Inv(9.00%)	INR	526.50
				SGST-Inv(9.00%)	INR	526.50
(430)	Sac : 995462 - Inst of 80mm CI spun P trap	2	NOS	900.00	1,800.00	
				CGST Inv(9.00%)	INR	162.00
				SGST-Inv(9.00%)	INR	162.00
(431)	Sac : 995462 - T&C of 80mm CI spun P trap	2	NOS	450.00	900.00	
				CGST Inv(9.00%)	INR	81.00
				SGST-Inv(9.00%)	INR	81.00
(432)	Sac : 995462 - Handover of 80mm CI spun P trap	2	NOS	225.00	450.00	
				CGST Inv(9.00%)	INR	40.50
				SGST-Inv(9.00%)	INR	40.50
(433)	Sac : 995462 - Supply of 100mm CI spun P trap (Toilet / Kit. / Duct / Balcony Waste line)	13	NOS	1,625.00	21,125.00	
				CGST Inv(9.00%)	INR	1,901.25
				SGST-Inv(9.00%)	INR	1,901.25
(434)	Sac : 995462 - Inst of 100mm CI spun P trap	13	NOS	500.00	6,500.00	
				CGST Inv(9.00%)	INR	585.00
				SGST-Inv(9.00%)	INR	585.00
(435)	Sac : 995462 - T&C of 100mm CI spun P trap	13	NOS	250.00	3,250.00	

Corporate Addr.:514, Dalomal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	292.50
				SGST-Inv(9.00%)	INR	292.50
(436)	Sac : 995462 - Handover of 100mm CI spun P trap	13	NOS	125.00		1,625.00
				CGST Inv(9.00%)	INR	146.25
				SGST-Inv(9.00%)	INR	146.25
(437)	Sac : 995462 - Supply of 150mm UPVC/PP NRV Providing, fixing, Testing and Commissioning of UPVC / PP manually operated backflow preventer (NRV) for rain water lines discharging to main SWD / Nulla from DCB. Including construction of valve chamber of 900 x 600 size as per company specifications and P & F of Heavy duty D.I. cover 104 kg (Item code no = C-250 / MR 17), including excavation in any type of soil . (Chamber / civil items considered separately in respective items) (To be confirm before order)	1	NOS	8,775.00		8,775.00
				CGST Inv(9.00%)	INR	789.75
				SGST-Inv(9.00%)	INR	789.75
(438)	Sac : 995462 - Inst of 150mm UPVC/PP NRV	1	NOS	2,700.00		2,700.00
				CGST Inv(9.00%)	INR	243.00
				SGST-Inv(9.00%)	INR	243.00
(439)	Sac : 995462 - T&C of 150mm UPVC/PP NRV	1	NOS	1,350.00		1,350.00
				CGST Inv(9.00%)	INR	121.50
				SGST-Inv(9.00%)	INR	121.50
(440)	Sac : 995462 - Handover of 150mm UPVC/PP NRV	1	NOS	675.00		675.00
				CGST Inv(9.00%)	INR	60.75
				SGST-Inv(9.00%)	INR	60.75

Corporate Addr.:514, Dalmal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value
(441)	Sac : 995462 - Supply of Domestic water pump (H103M) PUMPS AND EQUIPMENTS Supply, Installing, testing and commissioning of Water Transfer Pump for OH Tank Filling Vertical inline multistage centrifugal pump. Each pump shall have TEFC 2900 RPM, IE3 Rating efficiency, three phase electric motor. The pump shall have cast iron head & base with SS Shaft/ Impeller/ Intermediate chamber. Pump shall be provided with mechanical seal. The pump shall be suitable for auto/ manual operation. Accessories like NRVs, isolating valves, suction and delivery header / piping, pressure gauge, MS base frame (Synthetic enamel painted over a coat of primer) has to be provided. (Quantities of Valves / pipe / gauges etc. considered in respective BOQ Items). Making Suitable cement concrete foundation with cement plaster for pumps with supply & fixing of required Anti vibration rubber pads (150mm x 150mm x 25mm thk. = 4 nos. per pump) and foundation bolts for pumps Bolt Sizes : a) Upto 10 HP Pump - 12mm Ø, b) 10 HP to 50 HP Pump - 16 mm Ø, c) Above 50 HP Pump - 20 mm Ø, d) As per pump manufacturers requirement. Flow rate : 535.33 LPM Head : 103 Mts Purpose : Domestic Water transfer (1 Set = 1W+1SB) Pump selected are, Kirloskar make Multistage Vertical inline pump , Model # KCIL32-08-2, 8 stages, 77.73% efficiency, 2900 RPM, Pump coupled with 20 HP, 3 Phase, 50 Hz, 415v electric motor(IE3) Having capacity 32120 LPH / 535.33 LPM / 8.92 LPS. at 103 meter head. OR Lubi make Multistage Vertical inline pump , Model # LCR32-08-2, 8 stages, 75.93% efficiency 2900 RPM, Pump coupled with 20 HP, 3 Phase, 50 Hz, 415v electric motor(IE3) Having capacity 32120 LPH / 535.33 LPM / 8.92 LPS. at 103 meter head. OR Wilo Mather + Platt make Multistage Vertical inline pump , Model # HELIX FIRST V3606/2-5/25/E/KS/415-50, 2900 RPM, Pump coupled with 20 HP, 3 Phase, 50 Hz, 415v electric motor(IE3) Having capacity 32120 LPH / 535.33 LPM / 8.92 LPS. at 103 meter head.	1	NOS	256,750.00	256,750.00
<hr/>					
CGST Inv(9.00%) INR 23,107.50					
SGST-Inv(9.00%) INR 23,107.50					

Corporate Addr.:514, Dalmal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021. Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
(442)	Sac : 995462 - Inst of Domestic water pump (H103M)	1	NOS	79,000.00	79,000.00	
				CGST Inv(9.00%)	INR	7,110.00
				SGST-Inv(9.00%)	INR	7,110.00
(443)	Sac : 995462 - T&C of Domestic water pump (H103M)	1	NOS	39,500.00	39,500.00	
				CGST Inv(9.00%)	INR	3,555.00
				SGST-Inv(9.00%)	INR	3,555.00
(444)	Sac : 995462 - Handover of Domestic water pump (H103M)	1	NOS	19,750.00	19,750.00	
				CGST Inv(9.00%)	INR	1,777.50
				SGST-Inv(9.00%)	INR	1,777.50

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value
(445)	Sac : 995462 - Supply of Flushing water pump (H99M) Flow rate : 268 LPM Head : 99 Mts Purpose : Flushing Water transfer (1 Set = 1W+1SB) Pump selected are, Kirloskar make Multistage Vertical inline pump , Model # KCIL 15-09, 9 stages, 70.99% efficiency, 2900 RPM, Pump coupled with 10 HP, 3 Phase, 50 Hz, 415v electric motor(IE3) Having capacity 16080 LPH / 268 LPM / 4.46 LPS. at 99 meter head. OR Lubi make Multistage Vertical inline pump , Model # LCR15-09, 9 stages, 71.46% efficiency 2900 RPM, Pump coupled with 10 HP, 3 Phase, 50 Hz, 415v electric motor(IE3) Having capacity 16080 LPH / 268 LPM / 4.46 LPS. at 99 meter head. OR Wilo Mather + Platt make Multistage Vertical inline pump . Model # HELIX FIRST V1610-5/25/E/KS/415-50, 2900 RPM, Pump coupled with 10 HP, 3 Phase, 50 Hz, 415v electric motor(IE3) Having capacity 16080 LPH / 268 LPM / 4.46 LPS. at 99 meter head. Supply, installing, testing and commissioning of Skid mounted terrace booster system with suction & delivery header complete including necessary valves, NRV's, air vessel, electrical panel, dry run protection etc. Each pump shall have TEFC 2900 RPM, IE3 Rating efficiency, three phase electric motor. The pump shall have cast Iron head & base with SS Shaft/ Impeller/ Intermediate chamber. Pump shall be provided with mechanical seal. System shall operate on Auto mode. (other than skid mounted system Valves / pipe / gauges etc. quantities are considered in respective BOQ items). Making Suitable cement concrete foundation with cement plaster for pumps with supply & fixing of required Anti vibration rubber pads (150mm x 150mm x 25mm thk. = 4 nos. per pump) and foundation bolts for pumps Bolt Sizes : a) Upto 10 HP Pump - 12mm Ø, b) 10 HP to 50 HP Pump - 16 mm Ø, c) Above 50 HP Pump - 20 mm Ø, d) As per pump manufacturers requirement. To be order only after confirmation from HOH team.	1	NOS	141,700.00	141,700.00
				CGST Inv(9.00%)	INR 12,753.00
				SGST-Inv(9.00%)	INR 12,753.00
(446)	Sac : 995462 - Inst of Flushing water pump (H99M)	1	NOS	43,600.00	43,600.00
				CGST Inv(9.00%)	INR 3,924.00



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				SGST-Inv(9.00%)	INR	3,924.00
(447)	Sac : 995462 - T&C of Flushing water pump (H99M)	1	NOS	21,800.00	21,800.00	
				CGST Inv(9.00%)	INR	1,962.00
				SGST-Inv(9.00%)	INR	1,962.00
(448)	Sac : 995462 - Handover of Flushing water pump (H99M)	1	NOS	10,900.00	10,900.00	
				CGST Inv(9.00%)	INR	981.00
				SGST-Inv(9.00%)	INR	981.00
(449)	Sac : 995462 - Supply of Irrigation system pump Fixing, jointing and testing including labour for fixing in position Irrigation pumps with supply and fixing of required Anti vibration rubber pads (150mm x 150mm x 25mm thk. = 4 nos. per pump) and foundation bolts for pumps Bolt Sizes : a) Upto 10 HP Pump - 12mm Ø, b) 10 HP to 50 HP Pump - 16 mm Ø, c) Above 50 HP Pump - 20 mm Ø including making concrete foundation for pumps. Valves and piping considered in respective BOQ items.	1	NOS	16,250.00	16,250.00	
	Irrigation system pumps (1W+1SB)			CGST Inv(9.00%)	INR	1,462.50
				SGST-Inv(9.00%)	INR	1,462.50
(450)	Sac : 995462 - Inst of Irrigation system pump	1	NOS	5,000.00	5,000.00	
				CGST Inv(9.00%)	INR	450.00
				SGST-Inv(9.00%)	INR	450.00
(451)	Sac : 995462 - T&C of Irrigation system pump	1	NOS	2,500.00	2,500.00	
				CGST Inv(9.00%)	INR	225.00
				SGST-Inv(9.00%)	INR	225.00
(452)	Sac : 995462 - Handover of Irrigation system pump	1	NOS	1,250.00	1,250.00	
				CGST Inv(9.00%)	INR	112.50
				SGST-Inv(9.00%)	INR	112.50



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value
(453)	Sac : 995462 - Supply of MCC Plumbing panel ELECTRICAL PANELS AND CABLES	1	NOS	204,750.00	204,750.00
<p>Design, fabrication, assembling, wiring, supply, installation, testing and commissioning of following Wall mounted / Floor mounted (including base stand200 mm height) motor control centre, shall be fabricated out of 14 gauge CRCA sheet steel in form in 3b formation with reinforcement of suitable size angle iron, channel 'T' sections irons and/or flats wherever necessary. Cable gland plates shall be provided on top as well as at the bottom of the panels. The indoor panels shall be IP 42 and outdoor panels shall be IP 54 type. The Panel shall have proper space with required clearance for cables, incoming / outgoing switchgear, CTs, PTs, ammeter, Voltmeter, selector switches, Insulated and properly supported compartmentalized bus bars with heat shrinkable sleeves along with the other control circuit accessories within the panel and any other electrical component mentioned in the Panel SLD.</p> <p>The Panel shall have seven tank pre treatment process comprising of degreasing, rinsing, de-rusting, rinsing, phosphatizing, rinsing and passivation followed by powder coat painting having a paint thickness of 60 microns or as specified. The Panel shall be Dust/Vermin proof. Painting as per specifications with 2 coats of red oxide primer and final approved shade of powder coated paint. 2 Nos. earthing terminals shall be provided for 3 phase, 4 wire, 50 Hz supply system. Lifting hooks shall also be provided in case of large panels.as per attached SLD & BOM.</p> <p>Water Level senser Shall be there in UG and overhead tanks to get Pumps on off Command to the system.</p>					
MCC #PLUMBING PANEL (plant room)					
<p>Incomer</p> <p>160A TP+N MCCB with MP Based OL,SC,ST Releases,</p> <p>Aux. 25KA & RHOM</p> <p>R Y B, Indicating Lamps</p> <p>Off On Trip Indicating Lamp</p> <p>Digital Multi Data Meter with RS 485Port BMS Compatible</p> <p>Current Transformer 150/5A CL.-1 5VA</p> <p>Digital Earth Leakage Relay with CBCT</p> <p>Control MCB 6A TP 10KA C Curve</p> <p>Necessary aux. contact of the I/C MCCB's Off,On,Trip status to BMS</p> <p>Bus Bar</p> <p>160 amps TPN (25KA) aluminium bus bar with heat shrinkable insulation sleeves.</p> <p>Outgoings</p> <p>2 Nos. TP MPCB with 20 HP Star delta starter as per type -2 coordination (1 set - 1W+1SB) as outgoing feeder to Domestic transfer pump. Each compartment shall contain CT operated digital electronic ammeter of 0-50 amps</p>					



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value
	range with auto/manual selector switch, on/off push button ,SPP and indicating lamps with MCB's , 'ON/OFF/TRIP' status of motor.				
	2 Nos. TP MPCB with 10 HP Star delta starter as per type -2 coordination (1 set - 1W+1SB) as outgoing feeder to Flushing transfer pump. Each compartment shall contain CT operated digital electronic ammeter of 0-50 amps range with auto/manual selector switch, on/off push button ,SPP and indicating lamps with MCB's , 'ON/OFF/TRIP' status of motor.				
	(Provision) 2 Nos. TP MPCB with 2.0 HP Direct on line starter as per type -2 coordination (1 set - 1W+1S) as outgoing feeder to Skid mounted terrace Booster System pumps for Domestic. Each compartment shall contain CT operated digital electronic ammeter of 0-10 amps range with auto/manual selector switch, SPP and indicating lamps with MCB's and 'ON/OFF/TRIP' status of motor				
	Spare MCCB's of following capacities:				
	63 amps TPN MCCB 1 No with TM based OL ,SC Release, Aux 25KA & RHOM with on off indicating lamp with control MCB, 6A SP 10KA C curve.				
	40 amps TPN MCB 1 No 10KA C Curve, - 01 nos				
	25 amps TPN MCB 1 No 10KA C Curve, - 01 nos				
	Necessary cable alleys, internal wiring, and interlocking, earthing for all equipment shall also included.				
	Notes:				
	All MCCBs shall be of 25KA breaking capacity and suitable for motor duty application.				
	Provision shall be made for providing potential free contacts to all pumps starters for connection to building automation system.				
	Provision shall be made for cyclic operation of Domestic & Flushing Pumps in auto mode, i.e. Standby pump shall also operate at an regular interval in auto mode, Sequence timer for pump operation shall be provided.				
	Provision shall be made to ensure system protection from dry running of the pump				
	All motor MCCB/protecting devices shall be as per TYPE -2 co-ordination.				
	Water level controller with sensor, float switch to be provided with Panel.				
	All Panels should be dispatched at site only after				
Corporate Addr.:514, Dalmal Tower, 211 FPJ Marg,Nariman Point, Mumbai- 400021, Tel No.					
Page No. : 67 / 88 -> 4700157988					
					

Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value
	inspection at manufacturer workshop by representatives of HOH electrical department. Cost of traveling (i.e.- contractor to make to & fro arrangements for transportation), testing etc. shall be borne by the Contractor. Any Panel dispatched without inspection is bound for rejection.				
MCC #PLUMBING PANEL AS DESCRIBED ABOVE					
				CGST Inv(9.00%)	INR 18,427.50
				SGST-Inv(9.00%)	INR 18,427.50
(454) Sac : 995462 - Inst of MCC Plumbing panel		1	NOS	63,000.00	63,000.00
				CGST Inv(9.00%)	INR 5,670.00
				SGST-Inv(9.00%)	INR 5,670.00
(455) Sac : 995462 - T&C of MCC Plumbing panel		1	NOS	31,500.00	31,500.00
				CGST Inv(9.00%)	INR 2,835.00
				SGST-Inv(9.00%)	INR 2,835.00
(456) Sac : 995462 - Handover of MCC Plumbing panel		1	NOS	15,750.00	15,750.00
				CGST Inv(9.00%)	INR 1,417.50
				SGST-Inv(9.00%)	INR 1,417.50
(457) Sac : 995462 - Supply of 3CX10sqmm Cu Arm cable Supplying & laying of following 1100 volt grade XLPE insulated aluminium / copper conductor armoured cables having outer sheath of fire retardent extruded (FRLS) compound as per specification in existing trenches, cable trays, ducts over bed of sand, clamped to wall with suitable clamps, saddles fixing bolts including connecting testing and commissioning. All cables to be labelled (black anodized) at both the ends.		100	M	312.00	31,200.00
				CGST Inv(9.00%)	INR 2,808.00
				SGST-Inv(9.00%)	INR 2,808.00
(458) Sac : 995462 - Inst of 3CX10sqmm Cu Arm cable		100	M	96.00	9,600.00
				CGST Inv(9.00%)	INR 864.00
				SGST-Inv(9.00%)	INR 864.00
(459) Sac : 995462 - T&C of 3CX10sqmm Cu Arm cable		100	M	48.00	4,800.00
				CGST Inv(9.00%)	INR 432.00
Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point, Mumbai- 400021, Tel No.					
Page No. : 68 / 88 -> 4700157988					
					

Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				SGST-Inv(9.00%)	INR	432.00
(460)	Sac : 995462 - Handover of 3CX10sqmm Cu Arm cable	100	M	24.00	2,400.00	
				CGST Inv(9.00%)	INR	216.00
				SGST-Inv(9.00%)	INR	216.00
(461)	Sac : 995462 - Supply of 3CX4sqmm Cu Arm cable	150	M	134.55	20,182.50	
				CGST Inv(9.00%)	INR	1,816.43
				SGST-Inv(9.00%)	INR	1,816.43
(462)	Sac : 995462 - Inst of 3CX4sqmm Cu Arm cable	150	M	41.40	6,210.00	
				CGST Inv(9.00%)	INR	558.90
				SGST-Inv(9.00%)	INR	558.90
(463)	Sac : 995462 - T&C of 3CX4sqmm Cu Arm cable	150	M	20.70	3,105.00	
				CGST Inv(9.00%)	INR	279.45
				SGST-Inv(9.00%)	INR	279.45
(464)	Sac : 995462 - Handover of 3CX4sqmm Cu Arm cable	150	M	10.35	1,552.50	
				CGST Inv(9.00%)	INR	139.73
				SGST-Inv(9.00%)	INR	139.73
(465)	Sac : 995462 - Supply of 3CX6sqmm Cu Arm cable	100	M	196.95	19,695.00	
				CGST Inv(9.00%)	INR	1,772.55
				SGST-Inv(9.00%)	INR	1,772.55
(466)	Sac : 995462 - Inst of 3CX6sqmm Cu Arm cable	100	M	60.60	6,060.00	
				CGST Inv(9.00%)	INR	545.40
				SGST-Inv(9.00%)	INR	545.40
(467)	Sac : 995462 - T&C of 3CX6sqmm Cu Arm cable	100	M	30.30	3,030.00	
				CGST Inv(9.00%)	INR	272.70
				SGST-Inv(9.00%)	INR	272.70
(468)	Sac : 995462 - Handover of 3CX6sqmm Cu Arm cable	100	M	15.15	1,515.00	
				CGST Inv(9.00%)	INR	136.35
				SGST-Inv(9.00%)	INR	136.35
(469)	Sac : 995462 - Supply of 4CX4sqmm Cu Arm cable	200	M	165.75	33,150.00	
				CGST Inv(9.00%)	INR	2,983.50

Corporate Addr.:514, Dalmal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				SGST-Inv(9.00%)	INR	2,983.50
(470)	Sac : 995462 - Inst of 4CX4sqmm Cu Arm cable	200	M	51.00	10,200.00	
				CGST Inv(9.00%)	INR	918.00
				SGST-Inv(9.00%)	INR	918.00
(471)	Sac : 995462 - T&C of 4CX4sqmm Cu Arm cable	200	M	25.50	5,100.00	
				CGST Inv(9.00%)	INR	459.00
				SGST-Inv(9.00%)	INR	459.00
(472)	Sac : 995462 - Handover of 4CX4sqmm Cu Arm cable	200	M	12.75	2,550.00	
				CGST Inv(9.00%)	INR	229.50
				SGST-Inv(9.00%)	INR	229.50
(473)	Sac : 995462 - Supply of 3CX10sqmm Cu End termination	8	NOS	234.00	1,872.00	
	Supply & fixing of Cable end termination of the following XLPE insulated aluminium/copper conductor armoured cables of 1100 volt grade including supplying and fixing of bimetallic crimping lugs, double compression glands with earthing facility and cable sockets etc, complete as required.			CGST Inv(9.00%)	INR	168.48
				SGST-Inv(9.00%)	INR	168.48
(474)	Sac : 995462 - Inst of 3CX10sqmm Cu End termination	8	NOS	72.00	576.00	
				CGST Inv(9.00%)	INR	51.84
				SGST-Inv(9.00%)	INR	51.84
(475)	Sac : 995462 - T&C of 3CX10sqmm Cu End termination	8	NOS	36.00	288.00	
				CGST Inv(9.00%)	INR	25.92
				SGST-Inv(9.00%)	INR	25.92
(476)	Sac : 995462 - Handover of 3CX10sqmm Cu End termination	8	NOS	18.00	144.00	
				CGST Inv(9.00%)	INR	12.96
				SGST-Inv(9.00%)	INR	12.96
(477)	Sac : 995462 - Supply of 3CX4sqmm Cu End termination	4	NOS	172.25	689.00	
				CGST Inv(9.00%)	INR	62.01

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				SGST-Inv(9.00%)	INR	62.01
(478)	Sac : 995462 - Inst of 3CX4sqmm Cu End termination	4	NOS	53.00		212.00
				CGST Inv(9.00%)	INR	19.08
				SGST-Inv(9.00%)	INR	19.08
(479)	Sac : 995462 - T&C of 3CX4sqmm Cu End termination	4	NOS	26.50		106.00
				CGST Inv(9.00%)	INR	9.54
				SGST-Inv(9.00%)	INR	9.54
(480)	Sac : 995462 - Handover of 3CX4sqmm Cu End termination	4	NOS	13.25		53.00
				CGST Inv(9.00%)	INR	4.77
				SGST-Inv(9.00%)	INR	4.77
(481)	Sac : 995462 - Supply of 3CX6sqmm Cu End termination	8	NOS	195.00		1,560.00
				CGST Inv(9.00%)	INR	140.40
				SGST-Inv(9.00%)	INR	140.40
(482)	Sac : 995462 - Inst of 3CX6sqmm Cu End termination	8	NOS	60.00		480.00
				CGST Inv(9.00%)	INR	43.20
				SGST-Inv(9.00%)	INR	43.20
(483)	Sac : 995462 - T&C of 3CX6sqmm Cu End termination	8	NOS	30.00		240.00
				CGST Inv(9.00%)	INR	21.60
				SGST-Inv(9.00%)	INR	21.60
(484)	Sac : 995462 - Handover of 3CX6sqmm Cu End termination	8	NOS	15.00		120.00
				CGST Inv(9.00%)	INR	10.80
				SGST-Inv(9.00%)	INR	10.80
(485)	Sac : 995462 - Supply of 4CX4sqmm Cu End termination	2	NOS	211.25		422.50
				CGST Inv(9.00%)	INR	38.03
				SGST-Inv(9.00%)	INR	38.03
(486)	Sac : 995462 - Inst of 4CX4sqmm Cu End termination	2	NOS	65.00		130.00
				CGST Inv(9.00%)	INR	11.70

Corporate Addr.:514, Dalmal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				SGST-Inv(9.00%)	INR	11.70
(487)	Sac : 995462 - T&C of 4CX4sqmm Cu End termination	2	NOS	32.50	INR	65.00
				CGST Inv(9.00%)	INR	5.85
				SGST-Inv(9.00%)	INR	5.85
(488)	Sac : 995462 - Handover of 4CX4sqmm Cu End termination	2	NOS	16.25		32.50
				CGST Inv(9.00%)	INR	2.93
				SGST-Inv(9.00%)	INR	2.93
(489)	Sac : 995462 - Supply of 25x3mm GI Strip Supply and fixing of following Earthing, bare GI/copper tapes / wires including all necessary fixing accessories and effecting connections as per specifications.	160	M	66.95		10,712.00
				CGST Inv(9.00%)	INR	964.08
				SGST-Inv(9.00%)	INR	964.08
(490)	Sac : 995462 - Inst of 25x3mm GI Strip	160	M	20.60		3,296.00
				CGST Inv(9.00%)	INR	296.64
				SGST-Inv(9.00%)	INR	296.64
(491)	Sac : 995462 - T&C of 25x3mm GI Strip	160	M	10.30		1,648.00
				CGST Inv(9.00%)	INR	148.32
				SGST-Inv(9.00%)	INR	148.32
(492)	Sac : 995462 - Handover of 25x3mm GI Strip	160	M	5.15		824.00
				CGST Inv(9.00%)	INR	74.16
				SGST-Inv(9.00%)	INR	74.16
(493)	Sac : 995462 - Supply of 10Gauge GI Wire	100	M	10.08		1,008.00
				CGST Inv(9.00%)	INR	90.72
				SGST-Inv(9.00%)	INR	90.72
(494)	Sac : 995462 - Inst of 10Gauge GI Wire	100	M	3.10		310.00
				CGST Inv(9.00%)	INR	27.90
				SGST-Inv(9.00%)	INR	27.90
(495)	Sac : 995462 - T&C of 10Gauge GI Wire	100	M	1.55		155.00
				CGST Inv(9.00%)	INR	13.95

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.

Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				SGST-Inv(9.00%)	INR	13.95
(496)	Sac : 995462 - Handover of 10Gauge GI Wire	100	M	0.78		78.00
				CGST Inv(9.00%)	INR	7.02
				SGST-Inv(9.00%)	INR	7.02
(497)	Sac : 995462 - Supply of 8 Gauge GI Wire	160	M	13.98		2,236.80
				CGST Inv(9.00%)	INR	201.31
				SGST-Inv(9.00%)	INR	201.31
(498)	Sac : 995462 - Inst of 8 Gauge GI Wire	160	M	4.30		688.00
				CGST Inv(9.00%)	INR	61.92
				SGST-Inv(9.00%)	INR	61.92
(499)	Sac : 995462 - T&C of 8 Gauge GI Wire	160	M	2.15		344.00
				CGST Inv(9.00%)	INR	30.96
				SGST-Inv(9.00%)	INR	30.96
(500)	Sac : 995462 - Handover of 8 Gauge GI Wire	160	M	1.08		172.80
				CGST Inv(9.00%)	INR	15.55
				SGST-Inv(9.00%)	INR	15.55
(501)	Sac : 995462 - Supply of 150mm cable tray Design, Fabrication, Supply, Unloading, Handling, Installation, Commissioning of Perforated ladder type Cable Trays of Pre galvanised 02 mm thick : As per IS: 2062 /1079 & Galvanising : As per IS: 2629/4759 ,all accessories include. Ladder type cable trays of following sizes, suspended from ceiling or fixed vertically on wall / column as per route directed at site, as approved complete as per technical specifications, drawings & relevant standards & site conditions.	60	M	682.50		40,950.00
				CGST Inv(9.00%)	INR	3,685.50
				SGST-Inv(9.00%)	INR	3,685.50
(502)	Sac : 995462 - Inst of 150mm cable tray	60	M	210.00		12,600.00
				CGST Inv(9.00%)	INR	1,134.00
				SGST-Inv(9.00%)	INR	1,134.00
(503)	Sac : 995462 - T&C of 150mm cable tray	60	M	105.00		6,300.00
				CGST Inv(9.00%)	INR	567.00

Corporate Addr.:514, Dalmal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				SGST-Inv(9.00%)	INR	567.00
(504)	Sac : 995462 - Handover of 150mm cable tray	60	M	52.50		3,150.00
				CGST Inv(9.00%)	INR	283.50
				SGST-Inv(9.00%)	INR	283.50
(505)	Sac : 995462 - Supply of 300mm cable tray	30	M	747.50		22,425.00
				CGST Inv(9.00%)	INR	2,018.25
				SGST-Inv(9.00%)	INR	2,018.25
(506)	Sac : 995462 - Inst of 300mm cable tray	30	M	230.00		6,900.00
				CGST Inv(9.00%)	INR	621.00
				SGST-Inv(9.00%)	INR	621.00
(507)	Sac : 995462 - T&C of 300mm cable tray	30	M	115.00		3,450.00
				CGST Inv(9.00%)	INR	310.50
				SGST-Inv(9.00%)	INR	310.50
(508)	Sac : 995462 - Handover of 300mm cable tray	30	M	57.50		1,725.00
				CGST Inv(9.00%)	INR	155.25
				SGST-Inv(9.00%)	INR	155.25
(509)	Sac : 995462 - Supply of 100X50mm GI trunking	20	M	552.50		11,050.00
				CGST Inv(9.00%)	INR	994.50
				SGST-Inv(9.00%)	INR	994.50
(510)	Sac : 995462 - Inst of 100X50mm GI trunking	20	M	170.00		3,400.00
				CGST Inv(9.00%)	INR	306.00
				SGST-Inv(9.00%)	INR	306.00
(511)	Sac : 995462 - T&C of 100X50mm GI trunking	20	M	85.00		1,700.00
				CGST Inv(9.00%)	INR	153.00
				SGST-Inv(9.00%)	INR	153.00
(512)	Sac : 995462 - Handover of 100X50mm GI trunking	20	M	42.50		850.00
				CGST Inv(9.00%)	INR	76.50
				SGST-Inv(9.00%)	INR	76.50



Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.

Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value
(513)	Sac : 995462 - Supply of 80mm GI blank flange MISCELLANEOUS ITEMS	1	NOS	373.75	373.75
Providing and fixing G.I. blank flanges, making flanged joints with G.I. bolts, G.I. nuts, G.I. washers and rubber insertion 3 mm thick, testing the flange and joints etc, complete for pipes of following diameter, (for unused / spare plumbing sleeves of UG Tanks & Retaining wall)					
				CGST Inv(9.00%)	INR 33.64
				SGST-Inv(9.00%)	INR 33.64
(514)	Sac : 995462 - Inst of 80mm GI blank flange	1	NOS	115.00	115.00
				CGST Inv(9.00%)	INR 10.35
				SGST-Inv(9.00%)	INR 10.35
(515)	Sac : 995462 - T&C of 80mm GI blank flange	1	NOS	57.50	57.50
				CGST Inv(9.00%)	INR 5.18
				SGST-Inv(9.00%)	INR 5.18
(516)	Sac : 995462 - Handover of 80mm GI blank flange	1	NOS	28.75	28.75
				CGST Inv(9.00%)	INR 2.59
				SGST-Inv(9.00%)	INR 2.59
(517)	Sac : 995462 - Supply of 100mm GI blank flange	1	NOS	455.00	455.00
				CGST Inv(9.00%)	INR 40.95
				SGST-Inv(9.00%)	INR 40.95
(518)	Sac : 995462 - Inst of 100mm GI blank flange	1	NOS	140.00	140.00
				CGST Inv(9.00%)	INR 12.60
				SGST-Inv(9.00%)	INR 12.60
(519)	Sac : 995462 - T&C of 100mm GI blank flange	1	NOS	70.00	70.00
				CGST Inv(9.00%)	INR 6.30
				SGST-Inv(9.00%)	INR 6.30
(520)	Sac : 995462 - Handover of 100mm GI blank flange	1	NOS	35.00	35.00
				CGST Inv(9.00%)	INR 3.15
				SGST-Inv(9.00%)	INR 3.15
(521)	Sac : 995462 - Supply of 150mm GI blank flange	1	NOS	617.50	617.50

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	55.58
				SGST-Inv(9.00%)	INR	55.58
(522)	Sac : 995462 - Inst of 150mm GI blank flange	1	NOS	190.00	190.00	
				CGST Inv(9.00%)	INR	17.10
				SGST-Inv(9.00%)	INR	17.10
(523)	Sac : 995462 - T&C of 150mm GI blank flange	1	NOS	95.00	95.00	
				CGST Inv(9.00%)	INR	8.55
				SGST-Inv(9.00%)	INR	8.55
(524)	Sac : 995462 - Handover of 150mm GI blank flange	1	NOS	47.50	47.50	
				CGST Inv(9.00%)	INR	4.28
				SGST-Inv(9.00%)	INR	4.28
(525)	Sac : 995462 - Supply of 50mm puddle flange Fabrication, Supply, installation & fixing of puddle flanges, 600mm long for the storage tanks. The puddle flanges shall be fabricated out of MS pipes and plates as per the drawing enclosed and hot dipped galvanized before installations for O.H. Tanks including Fire Fighting Tanks.	17	NOS	1,023.75	17,403.75	
				CGST Inv(9.00%)	INR	1,566.34
				SGST-Inv(9.00%)	INR	1,566.34
(526)	Sac : 995462 - Inst of 50mm puddle flange	17	NOS	315.00	5,355.00	
				CGST Inv(9.00%)	INR	481.95
				SGST-Inv(9.00%)	INR	481.95
(527)	Sac : 995462 - T&C of 50mm puddle flange	17	NOS	157.50	2,677.50	
				CGST Inv(9.00%)	INR	240.98
				SGST-Inv(9.00%)	INR	240.98
(528)	Sac : 995462 - Handover of 50mm puddle flange	17	NOS	78.75	1,338.75	
				CGST Inv(9.00%)	INR	120.49
				SGST-Inv(9.00%)	INR	120.49
(529)	Sac : 995462 - Supply of 80mm puddle flange	2	NOS	1,576.25	3,152.50	
				CGST Inv(9.00%)	INR	283.73
				SGST-Inv(9.00%)	INR	283.73

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
(530)	Sac : 995462 - Inst of 80mm puddle flange	2	NOS	485.00	970.00	
				CGST Inv(9.00%)	INR	87.30
				SGST-Inv(9.00%)	INR	87.30
(531)	Sac : 995462 - T&C of 80mm puddle flange	2	NOS	242.50	485.00	
				CGST Inv(9.00%)	INR	43.65
				SGST-Inv(9.00%)	INR	43.65
(532)	Sac : 995462 - Handover of 80mm puddle flange	2	NOS	121.25	242.50	
				CGST Inv(9.00%)	INR	21.83
				SGST-Inv(9.00%)	INR	21.83
(533)	Sac : 995462 - Supply of 100mm puddle flange	8	NOS	2,323.75	18,590.00	
				CGST Inv(9.00%)	INR	1,673.10
				SGST-Inv(9.00%)	INR	1,673.10
(534)	Sac : 995462 - Inst of 100mm puddle flange	8	NOS	715.00	5,720.00	
				CGST Inv(9.00%)	INR	514.80
				SGST-Inv(9.00%)	INR	514.80
(535)	Sac : 995462 - T&C of 100mm puddle flange	8	NOS	357.50	2,860.00	
				CGST Inv(9.00%)	INR	257.40
				SGST-Inv(9.00%)	INR	257.40
(536)	Sac : 995462 - Handover of 100mm puddle flange	8	NOS	178.75	1,430.00	
				CGST Inv(9.00%)	INR	128.70
				SGST-Inv(9.00%)	INR	128.70
(537)	Sac : 995462 - Scaffolding for plumbing works in shaft Scaffolding for plumbing works in shaft (if required) with all safety measures for labourers working on scaffolding.	200	SFT	14.00	2,800.00	
				CGST Inv(9.00%)	INR	252.00
				SGST-Inv(9.00%)	INR	252.00

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value
(538)	<p>Sac : 995462 - All plumbing pipe label wroks as per above details as well as details and pictures shown in specifications.</p> <p>All plumbing pipe label wroks as per above details as well as details and pictures shown in specifications.</p> <p>(TA+NTA).</p> <p>All Toilets - Flushing / Domestic branch and All Kitchens - Domestic branch = 25%.</p> <p>Terrace loop & branch pipes, All OH Tank capacity details, names on cover, tank overflow / cleanouts etc. = 15%.</p> <p>Podium loop & branch pipes (where applicable), All UG Tank capacity details, names on cover, tank overflow / cleanouts etc. = 15%</p> <p>Domestic, Flushing, Sump pump, other pump details, all pump delivery lines = 15%</p> <p>Suspended CI Main & Branch drain lines = 15%</p> <p>Suspended PVC Main & Branch drain lines (terrace / surface drain / garden drain) = 15%</p>	1	AU	72,000.00	72,000.00
(539)	<p>Sac : 995462 - handover of Manual with 12 feet coil (Va Supply and handover of Manual (Hand) Drain Cleaning Tool with steel coil.</p> <p>Material to be handover to HOH Plumbing department with necessary test and warranty / guarantee certificates of manufacturer.</p>	2	NOS	900.00	1,800.00



Sr No.	Service Description	Order Qty.	UOM	Unit Price	Value	
				CGST Inv(9.00%)	INR	162.00
				SGST-Inv(9.00%)	INR	162.00
(540)	Sac : 995462 - handover of Manual with 25 feet coil (Va	2	NOS	1,150.00		2,300.00
				CGST Inv(9.00%)	INR	207.00
				SGST-Inv(9.00%)	INR	207.00
2	Managing of material loading + unloading Building : Oakwood Kalyan	1	AU			300,000.00
(541)	Sac : 995462 - Managing of material loading +	1	AU	300,000.00		300,000.00
				CGST Inv(9.00%)	INR	27,000.00
				SGST-Inv(9.00%)	INR	27,000.00
				Gross Price		16,864,933.60
				Discount %		0.00
				Net Price		16,864,933.60
				Tax Amount		3,035,688.52
				Grand Total		19,900,622.12

In Words : INR Rupees One Crore Ninety Nine Lakh Six Hundred and Twenty Two and Twelve paise only.

TERMS & CONDITIONS

1	Payment Terms	Due within 30 days
2	Defect Liability Period	Shall be for 12 Months after completion of works.
3	Price Validity	The rates should remain firm till the completion of contract.
4	Schedule	Attached, if Applicable
5	Samples to be approved	If Applicable
6	Complainces	As Attached in Annexure - I
7	Retention %	
8	Notes1	Proposed Residential / Commercial/ Infra Buildings at Oakwood, Woodspring Project at Kalyan allowed work for Plumbing & Sanitation work as per the approval mail dt 18.04.2025 and agreed upon.

DEFINITIONS:

GMBL shall mean Golden Mile Builders LLP. and include his heirs, executors, administrator and assigns (in case of sole proprietary firm) the Partner or Partners for the time being comprising the said firm, the survivor or survivors of them, the heirs, executors, administrators of the last surviving partner, his, her or their assigns (incase of partnership firm) the successors or assigns (in case of Limited Company).

Contractor shall mean M/s MADHURAM ENTERPRISES and includes executors, administrator and assigns.

Pls Note - Actual measurement to be taken on site

Corporate Addr.:514, Dalmal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



IMP . NOTE:

"All work should be done as per the approved work schedule. In case of any delay, refer to Clause No. 29 for penalty details."

- ü,,Contractors should confirm all sections before submitting their quotation.
- ü,,Contractor should follow the Safety system as per the company policy.
- ü,,Payment Term - 30 days from date of submission of Tax Invoice
- ü,,Work shall be executed as per specification & drawings & as directed by Engineer In Charge
- ü,,No space will be provided on site for Labour hutments / Stay.
- ü,,All local problems to be handled by the contractor.
- ü,,Electricity & construction water in client's scope.
- ü,,Pumps to be brought by the Contractors for dewatering purposes.
- ü,,Completion period : As per Schedule
- ü,,Escalation : Nil Fixed price contract
- ü,,Mobilization : N/A
- ü,,Materiel advance : N/A
- ü,,Payment terms : within 30 days
- ü,,Retention : 5% on every RA bill, will be released after completion of DLP.
- ü,,Defect liability period : 12months.
- ü,,Liquidated damage : 0.25% per week maximum upto 10%.

Payment Terms:-

- i) ..60% against material delivery at site.
- ii) ..20% against installation of works.
- iii) ..15% against testing, commissioning & Handing over.
- iv) ..5% against Tax Invoice after handing over
- v) ..5% of Retention money shall be deducted from each R.A. Bill and will release after DLP 12 Months. This balance retention money shall be refunded within one month of completion of DLP as specified in the contract.only after ensuring that all the defects are rectified by the contractor to the full satisfaction of the employer.
- vi) ..Provide MTC (Manufacturers Test Certificate) on site for all materials along with
,,challans.
- vii) ..Payment will be released within 30 days of inward dt of bill,
subject to the
,,clearance of statutory Labour Compliances from Company Compliance Officer.
,,Bills shall be cancelled if statutory Labour Compliances documents are not
submitted within the stipulated time.

GENERAL SCOPE OF WORK

- 1.,Scope of works as per Final Offer / BOQ as mentioned above &

Corporate Addr.:514, Dalomal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



subsequent discussions.

2.,It is clearly understood that Contractor have studied BOQ / Specification /

Make provided by GMBL and also Contractor have quoted for the make mentioned in the approved list and no further claim shall be entertained later on account of this by the GMBL.

3.,The specification mentioned in the Final Offer / BOQ is as per IS Standards and

best construction practices and same shall be followed by the Contractor.

4.,Completion Period: The Contractor shall complete the Scope of work as per approved Work Schedule including mobilization period

5.,The final quoted rate provided by the Contractor is inclusive of all wastages

and the Contractor shall not charge for any no additional wastage.

6.,Commencement of Work # The Contractor shall commence the work within 10 days from the date of issue of work order or notice to proceed whichever is earlier.

7.,Payment terms: Monthly Billing against work done at site due within 30 days

from the date of submission of Bill. Mobilization & Material Advance is not applicable for this Contract.

8.,As agreed, any additional items shall be charged with the cost of material +

labour + Plants & Tools + 15% for profits and overheads + all applicable taxes by the Contractor. For Non tendered items Amended Order shall be released within 45 days and shall be paid in subsequent RA Bills by the GMBL.

9.,Escalation # For all the items, final quoted rate is firm till completion of work

and escalation will not be considered under any circumstances.

10.,Final measurement will be certified as per the final laid quantity.

11., For the rate only items, rate will remains same and Quantities may vary.

12.,Mode of Measurement will be as per IS 1200.

13.,Final bill shall be scrutinized and settled in 30 Days of its presentation including the certification by the GMBL along with any balance works.

14.,For GMBL supply materials, reconciliation statement to be furnished along with the every bill if the actual wastage is more than the permissible wastage, the cost of excess wastage will be debited back @ 1.50 times of the actual cost of the materials.



15., Taxes & Duties # Individual item rate quoted is exclusive of GST. Any variation in the rate of taxes / duties, or imposition of new taxes / duties shall be reimbursed.

16., Retention Money - Retention money shall be deducted @ 5% from each R.A. Bill. The GMBL shall be free to set off the retention money against expenditure incurred by the GMBL in rectification of defects if the Contractor fails to attend to same to the satisfaction of the GMBL. This balance retention money shall be refunded within one month of completion of Defect Liability Period by the GMBL.

17., Electricity - The GMBL will provide 3 phase power supply at one point

18., Space for Labour Shed # No open Space for labour camp shall be provided within site premises by the GMBL.

19., All local problems shall be handled by the Contractor.

20., Variance in Scope of Work - Variance will be applicable to the overall contract value and not individual BOQ items. However the total contract value to be executed is subject to variation of plus or minus 15% (Fifteen Percent) of the contract value. For any work to be executed beyond +15 %, prior written permission to be taken by the Contractor from the GMBL.

21., Maintenance Period / Defects Liability Period - The Contractor shall be responsible for rectification of any genuine defect attributable on account of poor workmanship or materials brought and used and notified within defects liability period i.e. 12 months from the completion of Scope of Work. The responsibility of maintenance and upkeep of the structures against damages, losses etc during the defect liability period shall be taken care of by the GMBL.

22., Delay / Extension of Time - For any delay, the Contractor should write to the GMBL with reasons for delay within 7 days. Extension of time will be allowed based on the evaluation of reasons by the GMBL.

23., Statutory Requirements - as applicable time to time.

a) Insurance :

- 1) Work men Compensation insurance for workmen and subcontractors workmen.
- 2) Group personnel accident insurance to staff.
- 3) Automobile liability insurance.
- 4) Third party liability Insurance.
- 5) CAR Policy - for all the equipment/ Machineries/ Assets owned by the Contractor under the Scope of Work.

b) ..PF Statement / Challans or Remittance of previous period / Muster Roll / Wage register / Wage Slip, ECR Copy, Annual Return PF must be enclosed with each and every RA Bill,

c) ..Rates offered are inclusive of ESI as the same is applicable for construction industry.



d) ..Building & Construction Workers Act, 1996 # With respect to the enactment of the year 1999, construction workers should be registered under Building & Construction workers Act, 1996.

e) ..The Contractor shall declare and produce certified copies of all registration certificates as may be necessary from time to time including all statutory coverage and local laws.

f) ..Labour laws # The Contractor shall follow the provisions of ..Labour Laws as may be applicable time to time.

g) ..The GMBL reserves the right to withhold amount with respect ..to inadequate / non compliance of statutory requirement by ..the Contractor.

24.,,The Contractor to submit details of Plant and Equipment, Tools, Tackle proposed to be deployed for the execution of work with the descriptive literature, Organization Chart with details of Qualifications & Experience of Key Personnel proposed to be deployed for the work, Construction Schedule for the Completion of the work showing all activities and all major milestones, Quality Assurance Program, Safety manual and procedure on acceptance of Work order.

25.,,The Contractor shall depute senior and experienced Project Manager/ Supervisor full time at site along with other adequate staff as required.(Or as per site Encharge instruction)

26.,,The Contractor shall extent utmost value engineering /inputs to the GMBL in matters of various construction methods, sequencing, products, etc.

27.,,Withhold of Payments - on Failure of the Contractor to make payments properly and regularly to its own workers, to its Sub-Contractors, to its suppliers, or to nominated Sub-Contractors & If the delay of such payments is beyond acceptable limit, which results into delay in completion of Scope of Work, then the GMBL has a right to make such payments directly on behalf of the Contractor and deduct the same from consecutive RA Bill without any obligation on the part of the GMBL.

28.,,Safety: It is the responsibility of the Contractor to take care of all the necessary safety requirements and precautions to men and materials of the Contractor throughout the duration of the completion of the Scope of Work. The GMBL shall not be responsible for any loss due to death, theft, fire accidents or any other reasons, whatsoever happen at site. The Contractor shall be liable for payment of compensation arising out of the same and the Contractor shall indemnity to the GMBL for the same.

29.,,Liquidated Damages - Liquidated damages shall be levied @0.125% of the contract value per week or part thereof subject to a maximum of 5% (Five percent) of contract value. Liquidated damages will be calculated after considering suitable extensions of delays caused not attributable to the Contractor, in providing decisions at site / non issuance of GFC within reasonable time before the planned activity and delay due to force majeure stoppages.



30.,,Foreclosure - The Contractor shall be entitled to compensation for the work done, purchase made, terminal labor benefits and reasonable incidental expense if at any point of time after the site is fully mobilized and the project has to be stopped due to reasons not attributable to the Contractor. No loss on opportunity cost, loss of profit etc shall be payable by the GMBL.

31.,,Termination of Contract - The GMBL reserves the right to terminate the contract / work order by giving a 30 days' notice at its sole discretion without assigning any reason and in such an eventuality, the GMBL shall not be liable to pay any compensation to the Contractor. This has been clearly understood and agreed by the Contractor

32.,,Force Majeure - Neither party here to shall be held responsible for any delay or failure to perform any nor all the obligations imposed upon such party caused by Force Majeure. In such a case, the time for performance for such obligations and the obligations of the other party to the extent that they are directly affected by such occurrence will be extended by a period equal to that time.

Notification of circumstance of Force Majeure shall be given by letter /fax addressed to the other party within 15 working days of its occurrence. This letter /fax shall be confirmed by a letter within a week, along with a certificate of the relevant chamber of commerce, confirming the existence of the circumstances of the Force Majeure. Only the following shall be considered as Force Majeure, if they intervene before contractual delivery date and impede performance: Wars, Revolutions, Fire, floods, Epidemics, Pandemic, Earthquakes, and Quarantine restriction, Freight Embargoes, Strikes and Lockouts, Lockdowns imposed by the Government Authorities which directly affect the performance related to this contract. Unless otherwise directed by the GMBL, the Contractor shall continue to perform their obligations under the contract as far as practical, and shall seek all reasonable alternative means for performance not prevented by the Force Majeure event

33.,,ARBITRATION:

In the event any dispute or controversy between the Parties, which cannot be resolved amicably within 30 days of its being communicated in writing by either Party, shall be referred to Engineer # in #charge and if the Contractor is aggrieved by the decision taken by Engineer # in #charge then same shall be referred to arbitration in accordance with The Arbitration and Conciliation Act, 1996 and any modification thereto.

However, the Contractor shall be bound by interim or final decision taken by the Engineer-in-Charge and continue to perform its obligations under this Contract, unless the same is stayed, modified or reversed by any interim or final award/order of the Arbitrators.

Each party shall be entitled to nominate one arbitrator each and the two arbitrators shall jointly nominate a third presiding arbitrator. The parties agree that any arbitration award shall be final and binding upon the parties. In case the Parties do not come to mutual consent within 30 days, either Party can approach the Indian Council of Arbitration for appointing a Sole Arbitrator.



- # The place of arbitration shall be in Mumbai and the language of arbitration shall be English.
 - # The cost of arbitration shall be shared by the Parties as per Award.
 - # The parties hereto agree that, even though the dispute is referred to Arbitration, the Contractor shall be obliged to carry out their obligations under the Contract unless the Contract has already been repudiated or terminated. It is further clarified that the GMBL shall be entitled to retain any sum or portion of the Contract Sum which has become due and payable, for any unfinished works or any subject matter under arbitration till the final Award passed under Arbitration.
 - # During the period when a matter/dispute is referred to the decision of the Engineer-in-Charge and if thereafter the matter is referred to Arbitration, the Contractor shall be bound by interim or final decision taken by the Engineer-in-Charge and continue to perform its obligations under this Contract, unless the same is stayed, modified or reversed by any interim or final award/order of the Arbitrators.
34. Notes:
- # All notices, invoices, communication required to be sent under this Work Order by the Contractor to the GMBL shall be sent or delivered to GMBL at the address set forth herein Golden Mile Builders LLP.
- # GST TERMS & CONDITIONS:
- (a) "The Contractor hereby undertakes that the Contractor shall make timely payments of all taxes, duties, levies imposed by Government, be responsible for filing of all necessary tax returns and undertake all necessary compliances in accordance with applicable statutory requirements under the relevant Taxing Statute in relation to sum received from the GMBL.
 - (b) The Contractor hereby undertakes that it will issue the tax invoices within a period of 30 days from the date of completion of supply in the manner and with all the prescribed particulars as are required to be specified as per the Goods and Service Tax (Tax invoice, credit and debit note) Rules, 2017.
 - (c) The Contractor undertakes that any discount in relation to a supply, whether offered before or at the time of, or after the supply, will be specifically recorded in the tax invoice issued by the Contractor or clearly identified with each supply invoice in any other manner agreed upon.
 - (d) The Contractor hereby undertakes that 'the address / location' of the GMBL to which the invoice will be issued by the Contractor will be at the address as mentioned in hereinabove at Clause 36. Separately, prior to issue of an invoice, the Contractor shall intimate to the EIC of the GMBL about 'the address / location' of the GMBL to which the invoice will be issued and a prior approval from the EIC of the GMBL in this respect will be taken by the Contractor.
 - (e) The Contractor undertakes that a debit note/ supplementary invoice with appropriate references to the original invoice will be issued within 30 days from the date of intimation in this respect by the GMBL.

Corporate Addr.:514, Dalmal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.



- (f) The Contractor undertakes that a credit note with appropriate references to the original invoice will be issued within 30 days from the date of intimation in this respect by the GMBL.
- (g) The Contractor agrees that it is eligible to receive consideration towards a supply only after the correct details of supply are uploaded by the Contractor in the Form GSTR-1 which is subsequently reflected in Form GSTR-2A made available electronically to the GMBL. The Contractor also authorizes the GMBL to retain the payment of consideration to the Contractor till such time the correct details of supply are reflected in Form GSTR-2A made available electronically to the GMBL.
- (h) The Contractor agrees to indemnify the GMBL and keep it indemnified from and against any or all Liabilities, as defined in Explanation below, that accrues / demanded by Taxing Authority, in respect of or in connection with the execution of scope of work or payments made/due to the Contractor, arising under this Work Order or anything done pursuant to the same.
- (i) Such indemnification of Liabilities by the Contractor to GMBL shall be made within ten (10) days of the Liabilities accruing / demanded raised by Tax Authorities on the GMBL either by way of issuance of show cause notice or order or decree.



PREPARED BY (L1)	Approved By (L2)	Approved By (L3)	Approved By (L4)	RECEIVED & ACCEPTED
Santosh Bavaskar	Santosh Bavaskar	Ravindra Kunawat	Sunil Bhat	

Each Party will comply with all laws, rules and regulations applicable to the performance of its obligations under this 4700157988 including legislations concerning Goods and Services Tax ("GST"), and shall take registration under the provisions of GST law, remit applicable GST, upload necessary statements / returns, etc. in the time and manner prescribed and do all other necessary steps within the prescribed timeline so as to enable the Other Party to take input tax credit of the tax paid and shall also procure and maintain all other licenses and permits necessary for the performance of its obligations under this 4700157988. The Indemnifying Party shall protect the interests of Other Party and indemnify it against all claims, liabilities, costs, fines, penalties, fees, expenses, demands, claims, interests, losses including those arising due to the inability of the Other Party to claim the input tax credit of GST and for any tax, interest, penalty, that accrues or is demanded by any Tax Authority or proposed to be imposed either during investigation or any action, audit or by way of issuance of show cause notice, or demanded by way of issuance of order or decree by a Tax Authority, which Other Party may suffer or incur or face due to non-compliance of any law, rule and regulation applicable to the performance of the Indemnifying Party's obligations under this 4700157988 including legislations governing GST.

In the event of any change of law, regulation, including but not limited to introduction and implementation of GST in India or subsequent amendments to legislations governing GST, occurs during the tenure of this Agreement which results in any benefit / tax reduction / saving / concession to one Party, such Party shall be bound to pass on such benefit / reduction / saving / concession arising due to such change in the law or regulation to the Other Party. Each party agrees and accepts its obligation, including but not limited to obligation in terms of Section 171 of the Central Goods and Services Tax Act, 2017, that any reduction in rate of tax applicable to the performance of its obligations under this Agreement or the benefit of input tax credit accruing to one Party shall be passed on to the Other Party by way of commensurate reduction in prices.

Our company is not going to indemnify any liability that arises due to any kind of taxes / duties wrongly charged, non payment of tax to Government, disallowance of input tax credit, interest, penalties including and in relation to compliances arising under respective Taxing Statute in course of execution of scope of work.



PREPARED BY

The Total Value of this PO : **4700157988** is INR **19900622.12** (Rupees One Crore Ninety Nine Lakh Six Hundred and

AUTHORISED SIGNATORY(s)

Corporate Addr.:514, Dalmal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.

Twenty Two and Twelve paise only)

GSTIN : 27AATFG8069J1ZJ

CIN No : AAO-6315

Note :system generated and electronic signed

Corporate Addr.:514, Dalamal Tower, 211 FPJ Marg,Nariman Point,
Mumbai- 400021, Tel No.

Page No. : 87 / 88 > 4700157988



Annexure - I

1. Labour Law Compliance:
 - 1.1 The Contractor shall apply and obtain Labour Licence from the respective authority and renew the same from time to time under the Contract Labour (R&A) Act 1970. The Principal Employer will issue to the Contractor the necessary Form V under the said Act.
 - 1.2 The Contractor shall apply and obtain Registration Certificate from the respective authority under the Building and Other Construction Workers Act 1996.
 - 1.3 The Contractor shall make due compliance of the provisions under various Labour Laws and other enactments, notifications, regulations, rules etc. as applicable to him at the work site from time to time including and not limiting to Minimum Wages Act, Contract Labour Act, Provident Fund Act, Payment of Wages Act, Maharashtra / Tamilnadu / Karnataka / Andhra Pradesh HRA Act, Labour Welfare, Professional Tax and Building and Other Construction Workers Act, etc. wherever applicable depending on location of contract.
 - 1.4 The Contractor shall maintain records, registers, notices etc. as required under various Labour Laws and other enactments, notifications, regulations, rules etc. as applicable to him at the work site from time to time including and not limiting to Minimum Wages Act, Contract Labour Act, Provident Fund Act, Payment of Wages Act, Maharashtra / Tamilnadu / Karnataka / Andhra Pradesh HRA Act, Labour Welfare & Professional Tax and Building and Other Construction Workers Act & etc. wherever applicable depending on location of contract and produce the same to the representative of Company on demand.
 - 1.5 The Contractor shall produce following registration numbers / code numbers to the Principal employer upon awarding the work to him by the Principal Employer
 1. Provident Fund Code Number
 2. Maharashtra / Tamilnadu / Karnataka / Andhra Pradesh Labour Welfare Code Number wherever applicable depending on location of contract
 3. Professional Tax Registration
 - 1.6 The Contractor shall submit to the Principal Employer following registers and records maintained by him every month on the day and time as decided by the Principal Employer.
 1. Muster roll and wage register
 2. Registers, Notices, Returns etc. as prescribed under various Labour Laws applicable
 3. PF challans duly remitted
 4. PT challans duly remitted
 5. ESIC Challans duly remitted (Applicable w.e.f 01.08.2015)
 6. MLW/TLW/KLW/APLW wherever applicable depending on location of contract, fund challan duly remitted for the month of June & December
 - 1.7 The Contractor shall pay to his labour as per the Minimum Wage Rates as prescribed from time to time. The Contractor shall make the payment of wages in presence of the representative of Principal Employer and accordingly obtain his signature in the wage register for having done so.
 - 1.8 The Contractor shall execute deed of undertaking cum Indemnity on Rs. 200/- non judicial stamp paper duly notarised as per the annexure I to this document wherein he shall agree and undertake to abide by the provisions of various Labour Laws and the rules / regulations framed under the various Labour Laws as applicable and amended from time to time including and not limiting to Contract Labour (R&A) Act, Minimum Wages Act, Employees Provident Fund Act, Building and Other Construction Workers Act, etc. whilst carrying out the #Contract Work" with the help of labours engaged by him directly or through sub-contractors including gang workers. The Contractor shall further indemnify and keep indemnified the Principal Employer for all the time against any litigation and /or dispute and /or claim accrued out of contract of work and for recovery of penalties and damages levied by any authority from Principal Employer and the cost incurred by the Principal Employer due to any non-compliance by the Contractor, of the statutory requirements including and not limiting to Contract Labour (R&A) Act, Minimum Wages Act, Employees Provident Fund Act, Building and Other Construction Workers Act, etc.
 - 1.9 The Contractor shall abide by the rules and regulations existing during the contract period as applicable for the contractors at site.
 - 1.10 The Contractor shall abide by the Safety Regulations of the Company and as under the Building and Other Construction Workers Act. Failure to use safety equipment as required by our site supervisor will be a sufficient reason for cancellation of the Contract. All the site work may be suspended if it is found that the workmen are employing unsafe working practice and all the cost/ losses incurred due to the suspension of work shall be borne by the contractor.
 - 1.11 The Contractor shall take at all times due and proper precautions against accident and injury to any of the workers or to any person or persons or property whether arising from or occasioned by the operations or otherwise and shall forthwith repair, make good and defray and damage, loss, cost or charge which may have been occasioned to the works or to the Company or to any person or persons or property injuriously affected thereby and shall be indemnified and save harmless and keep indemnified the Company from and against all actions, suits, proceedings, claim and demands whatsoever by reason or on account thereof.
 - 1.10 The Contractor shall arrange to provide FIRST AID immediately to the injured employee.
 - 1.11 The Contractor shall deploy skilled workmen like riggers, scaffolders, welders, fitters, crane operators, other specialized equipment operators like welding machine, power generators etc. with sufficient past experience and skills on relevant jobs. The Electricians to be deployed on the job must have valid Wireman Licence.
 - 1.12 The Contractor shall put all efforts to deploy minimum manpower to execute the work awarded to him in stipulated time by using modern techniques and mechanization.
 - 1.13 The Contractor shall co-operate the company fully in formulating system / procedure to monitor / audit the due compliance made by him under various Labour Laws and other enactments, notifications, regulations, rules etc. as applicable to him at the work site from time to time.
 - 1.14 The Contractor shall produce before the Principal Employer a copy of Workmen Compensation Policy adequately covering the labours and staff engaged by him directly or through sub- contract for executing the work awarded.
 - 1.15 The bill of the Contractor shall be passed for payment on compliance of above by Contractor to the satisfaction of the representative appointed by the Principal Employer.

